

G.C.N.: **47-116-91** (30 кW) G.C.N.: **47-116-92** (35 кW)





# **ALTEAS ONE NET**

INSTALLATION AND SERVICING INSTRUCTIONS

kiwa approved product



CONDENSING WALL-HUNG GAS BOILER

Country of Destination: GB/IE



HOT WATER | HEATING | RENEWABLES

## INDEX

Overview	3
General Information	4
Advice for the Installer	4
CE Labelling	4
Data Plate Symbols	4
Safety Regulations	

Product description	7
Control Panel	
Display	8
Overall View	8
Overall Dimension	9
Minimum Clearances	9

Installation	10
Reference Standards	10
Installing the Boiler	13
Gas Connection	14
Water Connection	14
Instructions for Opening the Casing and Performing an	
Internal Inspection	14
Underfloor heating	15
Water circuit diagram	16
Connecting the Flue	17
Fitting the Coaxial Flue (Ø 60/100 Horizontal)	18
Fitting the 5" Flue (Ø 80/125 Horizontal / Vertical)	19
Fitting the Coaxial Flue (Ø 60/100 Vertical)	.20
Fitting the Twin Pipe (Ø 80/80)	21
Electrical Connections	.24
Peripheral Unit Connection	.24
Room Thermostat Connection	.25
Electrical Diagram	.26

Commissioning	. 27
Initial Preparation	. 27
Electricity Supply	. 27
Filling the Heating System	. 27
Filling of the DHW System	. 27
Gas Supply	. 27
Water Treatment	. 27
Start-up procedure	.29
First ignition	
(deaeration cycle and automatic calibration	.29
Maximum heating power adjustment	.33
Checking slow ignition power	.33
Heating ignition delay adjustment	. 33
Table summarising changes	.33
Gas changeover	
AUTO Function	.35
Boiler Protection Devices	.36
Boiler Protection Devices	.36
Table summarising error codes	. 37
Anti-Frost Device	. 37
Technical Area	.38
Accessing the Menus	.38
Maintenance	.45
General Comments	.45
Operational Test	.45
Draining procedures	45
Cleaning the primary exchanger	45
Cleaning the trap	.46
Maintenance Guide	. 47
General Access	, 47
Electrical Unit	48
Hydraulic Unit	50
Burner Unit	60

Technical Information	66
Technical Data GENUS ONE NET	66
ERP Data GENUS ONE NET	67
Product fiche GENUS ONE NET	68
Product fiche CUBE WIFI	68
Package Label - Instuctions to filling	69
Package fiche	70
Benchmark Commissioning Checklist	73
Benchmark Service Interval Record	74

Annual Maintenance......64

These instructions are suitable for Alteas One Net boilers : Do not forgot to complete the Benchmark Commissioning Checklist!



The Benchmark Scheme

Benchmark places responsibilities on both manufacturers and installers. The purpose is to ensure that customers are provided with the correct equipment for their needs, that it is installed, commissioned and serviced in accordance with the manufacturer's instructions by competent persons and that it meets the requirements of the appropriate Building Regulations. The Benchmark Checklist can be used to demonstrate compliance with Building Regulations and should be provided to the customer for future reference.

Installers are required to carry out installation, commissioning and servicing work in accordance with the Benchmark Code of Practice which is available from the Heating and Hotwater Industry Council who manage and promote the Scheme. Visit <u>www.centralheating.co.uk</u> for more information.

#### To The Installer

As part of the commissioning of this appliance it is vital that the Benchmark Commissioning Checklist is completed and given to the Householder. Please ensure that your customer is aware of the importance of keeping the Commissioning Checklist and Service Interval Record safe to document the product's history.

Please ensure that your customer is aware of the correct operation of the system, boiler and controls.

ARISTON recommend the use of protective clothing, when installing and working on the appliance i.e. gloves.

## **CUSTOMER CARE**

ARISTON, as a leading manufacturer of domestic and commercial water heating appliances is committed to providing high quality products and a high quality after sales service.

Advice on installation or servicing can also be obtained by contacting the ARISTON Technical and Customer Service Departments at High Wycombe.

TECHNICAL DEPARTMENT Tel: 0333 240 7777 Fax: 01494 459775 CUSTOMER SERVICE DEPARTMENT Tel: 0333 240 8777 Fax: 01494 459775

#### WARRANTY

The manufacturer's warranty is for 12 years from the date of purchase. The warranty is invalidated if the appliance is not installed in accordance with the recommendations made herein or in a manner not approved by the manufacturer. To assist us in providing you with an efficient after sales service, please register the warranty online at **www.ariston. co.uk** 

#### CAUTION

In the United Kingdom, installation, start-up, adjustments and maintenance, must be performed by a competent person only, in accordance with the current Gas Safety (Installation & Use) Regulations and the instructions provided.

In the Republic of Ireland, the installation and initial start up of the appliance must be carried out by a Competent Person in accordance with the current edition of I.S.813 "Domestic Gas Installations", the current Building Regulations, reference should also be made to the current ETCI rules for electrical installation.

All GAS SAFE registered installers carry a GAS SAFE ID card, and have a registration number. Both should be recorded in your boiler Benchmark Commissioning Checklist. You can check your installer is GAS SAFE registered by calling GAS SAFE directly on:- 0800 408 5500.

Improper installation may cause damage or injury to individuals, animals and personal property for which the manufacturer will not be held liable. To ensure efficient and safe operation it is recommended that the boiler is serviced annually by a competent person.

If it is known that a fault exists on the appliance, it must not be used until the fault has been corrected by a competent person.

Please refer to the terms and conditions of warranty in the user manual which are also available on our website.

This instruction booklet is especially designed for appliances installed in the UK and the Republic of Ireland

/3 🛆 ARISTON

## **ATTENTION!!**

THE INSTALLATION AND FIRST IGNITION OF THE BOILER MUST BE PERFORMED BY GAS SAFE REGISTERED ENGINEER IN COMPLIANCE WITH GAS SAFETY (INSTILLATION & USE) REGULATIONS AND ALL OTHER NATIONAL REGULATIONS REGARDING INSTALLATION, AND IN CONFORMITY WITH ANY REQUIREMENTS ESTABLISHED BY LOCAL AUTHORITIES AND PUBLIC HEALTH ORGANISATIONS.

AFTER THE BOILER HAS BEEN INSTALLED, THE INSTALLER MUST ENSURE THAT THE END USER RECEIVES THE DECLARATION OF CONFORMITY AND THE OPERATING MANUAL, AND SHOULD PROVIDE ALL NECESSARY INFORMATION AS TO HOW THE BOILER AND THE SAFETY DEVICES SHOULD BE HANDLED.

#### Advice for the installer

This appliance is designed to produce hot water for domestic use.

It should be connected to a heating system and a distribution network for domestic hot water, both of which must be compatible with its performance and power levels.

The use of the appliance for purposes other than those specified is strictly forbidden. The manufacturer cannot be held responsible for any damage caused by improper, incorrect and unreasonable use of the appliance or by the failure to comply with the instructions given in this manual.

Installation, maintenance and all other interventions must be carried out in full conformity with the governing legal regulations and the instructions provided by the manufacturer. Incorrect installation can harm persons, animals and possessions; the manufacturing company shall not be held responsible for any damage caused as a result. The boiler is delivered in a carton. Once you have removed all the packaging, make sure the appliance is intact and that no parts are missing. If this is not the case, please contact your supplier.

Keep all packaging material (clips, plastic bags, polystyrene foam, etc.) out of reach of children as it may present a potential hazard.

In the event of a fault and/or malfunction, turn the appliance off, turn off the gas cock and do not attempt to repair it yourself. Contact a qualified professional instead.

Before any maintenance or repair work is performed on the boiler, make sure you have disconnected it from the electricity supply by switching the external bipolar switch to the "OFF" position and removing the fuse.

All repairs, which should only be performed using original spare parts, should be carried out by a qualified professional. Failure to comply with the above instructions could compromise the safety of the appliance and invalidate all liability on the part of the manufacturer.

In the event of any maintenance or other structural work in the immediate vicinity of the ducts or flue gas exhaust devices and their accessories, switch the appliance off by switching the external bipolar switch to the "OFF" position and shutting off the gas control valve. When the work has been completed, ask a qualified technician to check the efficiency of the ducting and the devices.

Turn the boiler off and turn the external switch "OFF" to clean the exterior parts of the appliance.

Clean using a cloth dampened with soapy water. Do not use aggressive detergents, insecticides or toxic products. If the appliance is used in full compliance with current legislation, it will operate in a safe, environmentally-friendly and cost-efficient manner.

If using kits or optional extras, make sure they are authentic.


#### **CE** labelling

The CE mark guarantees that the appliance conforms to the following directives:

- 2016/426/EU
- relating to gas appliances
- 2014/30/EU
- relating to electromagnetic compatibility
- 92/42/CEE
- relating to energy efficiency
- 2014/35/EU relating to electrical safety
- 2009/125/CE Energy related Products
- 813/2013

Commission regulation (EU)

#### Symbols used on the data plate



#### Legend :

- 1. Brand
- 2. Manufacturer
- Boiler model Serial number
- 4. Commercial reference
- 5. Certification number
- 6. Destination country Gas category
- 7. Gas setting
- 8. Installation type
- 9. Electrical data
- 10. Maximum domestic hot water pressure
- 11. Maximum heating pressure
- 12. Boiler type
- 13. NOx class / Efficiency

- 14. Input rating nominal heating
- 15. Power ouput heating
- 16. DHW specific flow rate
- 17. Boiler output efficiency
- 18. Input rating nominal DHW
- 19. Gases which may be used
- 20. Minimum ambient temperature for use
- 21. Max. central heating temperature
- 22. Max. domestic hot water temperature

## SAFETY REGULATION

### Key to symbols:



Failure to comply with this warning implies the risk of personal injury, in some circumstances even fatal



Failure to comply with this warning implies the risk of damage, in some circumstances even serious, to property, plants or animals.

Install the appliance on a solid wall which is not subject to vibration.

Noisy operation.

When drilling holes in the wall for installation purposes, take care not to damage any electrical wiring or existing piping.

Electrocution caused by contact with live wires. Explosions, fires or asphyxiation caused 🔼 by gas leaking from damaged piping.

Damage to existing installations.



Flooding caused by water leaking from damaged piping.

Perform all electrical connections using wires which have a suitable section.

Fire caused by overheating due to electrical  $\bigwedge$ current passing through undersized cables.

Protect all connection pipes and wires in order to prevent them from being damaged.

Electrocution caused by contact with live wires. Explosions, fires or asphyxiation caused  $\checkmark$ by gas leaking from damaged piping.

Flooding caused by water leaking from damaged piping.

Make sure the installation site and any systems to which the appliance must be connected comply with the applicable norms in force.

Electrocution caused by contact with live wires which have been installed incorrectly.

Damage to the appliance caused by improper operating conditions.

Use suitable manual tools and equipment (make sure in particular that the tool is not worn out and that its handle is fixed properly); use them correctly and make sure they do not fall from a height. Replace them once you have finished using them.

Personal injury from the falling splinters or fragments, inhalation of dust, shocks, cuts, pricks and abrasions.

Damage to the appliance or surrounding objects caused by falling splinters, knocks and

## incisions.

Use electrical equipment suitable for its intended use (in particular, make sure that the power supply cable and plug are intact and that the parts featuring rotary or reciprocating motions are fastened correctly); use this equipment correctly; do not obstruct passageways with the power supply cable, make sure no equipment could fall from a height. Disconnect it and replace it safely after use.

Personal injury caused by falling splinters or fragments, inhalation of dust, knocks, 🗥 cuts, puncture wounds, abrasions, noise and vibration.

Damage to the appliance or surrounding objects caused by falling splinters, knocks and incisions.

Make sure any portable ladders are positioned securely, that they are suitably strong and that the steps are intact and not slippery and do not wobble when someone climbs them. Ensure someone provides supervision at all times.

Personal injury caused by falling from a height or cuts (stepladders shutting accidentally).



Make sure any rolling ladders are positioned securely, that they are suitably strong, that the steps are intact and not slippery and that the ladders are fitted with handrails on either side of the ladder and parapets on the landing.

Personal injury caused by falling from a height. /!\ During all work carried out at a certain height

(generally with a difference in height of more than two metres), make sure that parapets are used to surround the work area or that individual harnesses are used to prevent falls. The space where any accidental fall may occur should be free from dangerous obstacles, and any impact upon falling should be cushioned by semi-rigid or deformable surfaces.

Personal injury caused by falling from a height. Make sure the workplace has suitable hygiene

and sanitary conditions in terms of lighting, ventilation and solidity of the structures.

Personal injury caused by knocks, stumbling / etc.

Protect the appliance and all areas in the vicinity of the work place using suitable material.

Damage to the appliance or surrounding objects caused by falling splinters, knocks and <sup>2</sup> incisions.

### **OVERVIEW**

## Handle the appliance with suitable protection and with care.

Damage to the appliance or surrounding  $\triangle$  objects from shocks, knocks, incisions and squashing.

During all work procedures, wear individual protective clothing and equipment.

Personal injury caused by electrocution, falling splinters or fragments, inhalation of dust, shocks, cuts, puncture wounds, abrasions, noise and vibration.

Place all debris and equipment in such a way as to make movement easy and safe, avoiding the formation of any piles which could yield or collapse.

Damage to the appliance or surrounding objects from shocks, knocks, incisions and  $\Delta$  squashing.

All operations inside the appliance must be performed with the necessary caution in order to avoid abrupt contact with sharp parts.

Personal injury caused by cuts, puncture wounds and abrasions.

Reset all the safety and control functions affected by any work performed on the appliance and make sure they operate correctly before restarting the appliance.

Explosions, fires or asphyxiation caused by Agas leaks or an incorrect flue gas exhaust.

Damage or shutdown of the appliance caused by out-of-control operation.

Before handling, empty all components that may contain hot water, carrying out any bleeding if necessary.

Personal injury caused by burns.

Descale the components, in accordance with the instructions provided on the safety data sheet of the product used, airing the room, wearing protective clothing, avoid mixing different products, and protect the appliance and surrounding objects.

Personal injury caused by acidic substances coming into contact with skin or eyes; inhaling or swallowing harmful chemical agents.


Damage to the appliance or surrounding  $\triangle$  objects due to corrosion caused by acidic substances.

If you detect a smell of burning or smoke, keep clear of the appliance, disconnect it from the electricity supply, open all windows and contact the technician.

Personal injury caused by burns, smoke 🥂 inhalation, asphyxiation.

This appliance can be used by children aged from 8 years and above and  $\bigwedge$ person with reduced physical, sensory or mental capabilities or lack of experience and knowledge if they have been given supervision or instruction concerning use of the appliance in a safe way and understand the hazards involved. Children shall not play with the appliance. Cleaning and user maintenance shall not be made by children without supervision.


## **CONTROL PANNEL**



## **PRODUCT DESCRIPTION**


DISPLAY $\widehat{\begin{tabular}{c} $\mathcal{P}$ & $\mathbb{N}$ & $26/10/15 12:30 + $\mathcal{A}$ & $10^{\circ}$ -10^{\circ}$ \\ \hline $20,5^{\circ}$ & $0^{\circ}$ & $0^{\circ}$ & $0^{\circ}$ & $0^{\circ}$ & $10^{\circ}$ & $12^{\circ}$ & $14^{\circ}$ & $16^{\circ}$ & $18^{\circ}$ & $20^{\circ}$ & $22^{\circ}$ & $24^{\circ}$ \\ \hline $20,5^{\circ}$ & $0^{\circ}$ & $0^{\circ}$ & $0^{\circ}$ & $0^{\circ}$ & $10^{\circ}$ & $12^{\circ}$ & $14^{\circ}$ & $16^{\circ}$ & $18^{\circ}$ & $20^{\circ}$ & $22^{\circ}$ & $24^{\circ}$ \\ \hline $20,5^{\circ}$ & $0^{\circ}$ & $0^{\circ}$ & $0^{\circ}$ & $0^{\circ}$ & $10^{\circ}$ & $12^{\circ}$ & $14^{\circ}$ & $16^{\circ}$ & $18^{\circ}$ & $20^{\circ}$ & $22^{\circ}$ & $24^{\circ}$ \\ \hline $20,5^{\circ}$ & $0^{\circ}$ & $0^{\circ}$ & $0^{\circ}$ & $0^{\circ}$ & $10^{\circ}$ & $12^{\circ}$ & $14^{\circ}$ & $16^{\circ}$ & $18^{\circ}$ & $20^{\circ}$ & $22^{\circ}$ & $24^{\circ}$ \\ \hline $20,5^{\circ}$ & $10^{\circ}$ & $12^{\circ}$ & $10^{\circ}$ & $12^{\circ}$ & $14^{\circ}$ & $16^{\circ}$ & $18^{\circ}$ & $20^{\circ}$ & $22^{\circ}$ & $24^{\circ}$ \\ \hline $20,5^{\circ}$ & $10^{\circ}$ & $12^{\circ}$ & $10^{\circ}$ & $12^{\circ}$ & $14^{\circ}$ & $16^{\circ}$ & $18^{\circ}$ & $20^{\circ}$ & $22^{\circ}$ & $24^{\circ}$ \\ \hline $20,5^{\circ}$ & $10^{\circ}$ & $10^{\circ}$ & $10^{\circ}$ & $12^{\circ}$ & $14^{\circ}$ & $16^{\circ}$ & $18^{\circ}$ & $20^{\circ}$ & $22^{\circ}$ & $24^{\circ}$ \\ \hline $20,5^{\circ}$ & $10^{\circ}$ & $10^{\circ}$ & $10^{\circ}$ & $12^{\circ}$ & $14^{\circ}$ & $16^{\circ}$ & $18^{\circ}$ & $12^{\circ}$ & $14^{\circ}$ & $16^{\circ}$ & $18^{\circ}$ & $16^{\circ}$ & $16^{\circ}$$		
60° ( COMFORT Risca	I,5 bar 82° AUTO	
Date and time	26/10/15 12:30	
Keylock active		
D.H.W. set temperature and indication of the set temperature level	<u>≡42°</u> .≓	
C.H. set temperature and indication of the set temperature level	<u>70°</u>	
Warning scheduled maintenance	Je .	
Heating operation set		
Heating operation active		
D.H.W. operation set	۲.	
D.H.W. operation active	<b>H</b>	
Flame detected with indication of power used		
Digital pressure gauge (bar)	<u>1,5 bar</u>	
Scrolling text displaying operation as information	Central heating	
Error wsignals The display show the code and description	ALERT	
AUTO function activated	AUTO	
Hot Water Comfort activated CH Schedule programming		
(set display: boiler base - see user's menù)		
00 02 04 06 08 10 1	2 14 16 18 20 22 24	
CH Schedule programming (set display: boiler complete - see user's menù)		
Internal temperature displayed for set zone. (with bus device connected - optional)	20,5 <sup>9</sup> <sup>3</sup>	
External temperature displayed	<b>↓</b> 10°	
ECO mode	P	
WIFI active	((()-	
WIFI connected to the local network, but without access to the server	نې	
WIFI not configured	<u>Š</u> X	
Solar temperature probe connected - option	I∑97	

**Overall view** 




- 18. Modulating Fan
- 20. Combustion Analysis Test Point

#### **Overall Dimensions**



#### **Minimum clearances**

In order to allow easy access to the boiler for maintenance operations, The boiler must be installed in accordance with the clearances stated below.



## **INSTALLATION**

#### **Reference Standards**

In the United Kingdom, the installation and initial start-up of the boiler must be by a Gas Safe registered installer in accordance with the installation standards currently in effect, as well as with any and all local health and safety standards i.e. Gas Safe.

In the Republic of Ireland the installation and initial start-up of the appliance must be carried out by a Competent Person in accordance with the current edition of I.S.813 "Domestic Gas Installations" and the current Building Regulations, reference should also be made to the current ETCI rules for electrical installation.

The installation of this appliance must be in accordance with the relevant requirements of the Local Building Regulations, the current I.E.E. Wiring Regulations, the by-laws of the local authority, in Scotland, in accordance with the Building Standards (Scotland) Regulation and Health and Safety document No. 635, "Electricity at Work Regulations 1989" and in the Republic of Ireland with the current edition of I.S. 813 and the Local Building Regulations (IE).

#### C.O.S.H.H.

Materials used in the manufacture of this appliance are nonhazardous and no special precautions are required when servicing.

#### **Codes of Practice**

Installation should also comply with the following British Standards Code of Practice (refer to the most recent version):

## BS 7593: Treatment of water in domestic hot water central heating systems

- BS 5546: Installation of hot water supplies for domestic purposes
- BS 5440-1: Flues
- BS 5440-2: Air supply
- BS EN 12831 BS EN 14336:
  - Forced circulation hot water systems
- BS 6798: Installation of gas fired hot water boilers of rated input not exceeding 70kW
- BS 6891: Installation of low pressure gas pipes up to 28mm
- BS 7671: IEE Wiring Regulations
- BS 4814: Specification for expansion vessels
- BS 5482: Installation of L.P.G.
- Technical Bulletin TB143 Flue Gas Analysis

and in the Republic of Ireland in accordance with the following codes of practice:

#### I.S. 813 Domestic Gas Installations

Avoid installing the boiler where the air inlet can be polluted by chemical products such as chlorine (swimming pool area), or ammonia (hair dresser), or alkalin products (launderette).


#### Flue

Detailed information on flue assembly can be found in the **"Connecting the Flue"** section.

The boiler must be installed so that the flue terminal is exposed to the free passage of external air at all times and must not be installed in a place likely to cause nuisance. It must not be allowed to discharge into another room or space such as an outhouse or closed lean-to.

Condensing boilers have a tendency to form a plume of water vapour from the flue terminal due to the low temperature of the flue gasses. The terminal should therefore be located with due regard for the damage or discolouration that may occur to building within the vicinity and consideration must also be given to adjacent boundaries, openable windows should also be taken into consideration when siting the flue.

The minimum acceptable clearances are shown below:



- A Directly below an opening, window, etc 300 mm

75 mm

300 mm

- B Horizontally to an opening, window, etc 300 mm
- C Below gutters, soils pipes or drain pipes
- D Below eaves 200 mm
- E From vertical drain pipe or soil pipe 75 mm
- F From internal or external corner
- G Above ground, roof or balcony level 300 mm
- H From a surface facing the terminal 600 mm
- I From a terminal facing a terminal 1200 mm
- J Vertically from a terminal on the same wall 1500 mm
- K Horizontally from an terminal on the same wall 300 mm
- L Fixed by vertical flue terminal

Note: The flue must not be installed in a place likely to cause a nuisance and positioned to ensure that products of combustion do not discharge across a boundary

It may be necessary to protect the terminal with a guard, if this is the case it will be necessary to purchase a stainless steel terminal guard. Reference should be made to the Building Regulations for guidance.

#### Ventilation

The room in which the boiler is installed does not require specific ventilation. If the boiler is installed in a cupboard or compartment ventilation is not required for cooling purposes.

#### **Gas Supply**

The gas installation and tightness testing must be in accordance with the requirements of BS6891. Ensure that the pipe size is adequate for demand including other gas appliances on the same supply.

#### **Electrical Supply**

The appliance requires an earthed 230V - 50 Hz supply and must be in accordance with current I.E.E. regulations. It must also be possible to be able to completely isolate the appliance electrically. Connection should be via a 3 amp double pole fused isolating switch with contact separation of at least 3mm on both poles. Alternatively, a fused 3 amp, 3 pin plug and unswitched socket may be used, provided it is not used in a room containing a bath or shower. It should only supply the appliance.

#### Water Supply

The boiler is suitable for sealed systems only. The maximum working pressure for the appliance is 6 bar. All fittings and pipework for the appliance should be of the same standard. If there is a possibility of the incoming mains pressure exceeding 6 bar, particularly at night, then a suitable pressure limiting valve must be fitted.

The boiler is designed to provide hot water on demand to multiple outlets within the property. If there is a requirement for greater demands, for example if the boiler has several bathrooms and cloakrooms, a vented or unvented hot water storage system may be used.

#### Showers

Any shower valves used with the appliance should be of a thermostatic or pressure balanced type. Refer to the shower manufacturer for performance guidance and suitability.

#### **Flushing and Water Treatment**

The boiler is equipped with a stainless steel heat exchanger.

The detailed recommendations for water treatment are given in BS 7593 (Treatment of water in domestic hot water central heating systems); the following notes are given for general guidance.

If the boiler is installed on an existing system, any unsuitable additives must be removed.

Under no circumstances should the boiler be fired before the system has been thoroughly flushed; the flushing procedure must be in line with BS 7593.

We highly recommend the use of a flushing detergent appropriate for the metals used in the circuit.

In hard water areas or where large quantities of water are in the system the treatment of water to prevent premature scaling of the main exchanger is necessary.

The formation of scale heat compromises the efficiency of the thermic exchanger because small areas of scale cause a high increase of the temperature of the metallic walls and therefore add to the thermal stress of the heat exchanger.

Demineralised water is more aggressive so in this situation it is necessary to treat the water with an appropriate corrosion inhibitor.

Any treatment of water by additives in the system for frost protection or for corrosion inhibition has to be absolutely suitable for all metals used in the circuit. The use of a corrosion inhibitor in the sysem is recommended to prevent corrosion (sludge) damaging the boiler and system;

If anti-freeze substances are to be used in the system, check carefully that they are compatible with the metals used in the circuit.

ARISTON suggests the use of suitable anti-freeze products, which will prevent rust and incrustation taking place.

Periodically check the pH balance of the water/anti-freeze mixture of the boiler circuit and replace it when the amount measured is out of the range stipulated by the manufacturer (7 < pH < 8).

DO NOT MIX DIFFERENT TYPES OF ANTI-FREEZE

In under-floor systems, the use of plastic pipes without protection against penetration of oxygen through the walls can cause corrosion of the systems metal parts (metal piping, boiler etc), through the formation of oxides and bacterial agents.

To prevent this problem it is necessary to use pipes with an "oxygen proof barrier", in accordance with standards DIN 4726/4729. If pipes of this kind are not used, keep the system separate by installing heat exchangers of those with a specific system water treatment.

Ariston suggests the installation of a magnetic filter on every installation.

#### IMPORTANT

Failure to carry out the water treatment procedure will invalidate the appliance warranty.

#### System Controls

The boiler is electrically controlled and is suitable for most modern electronic time and temperature controls. The addition of such external controls can be beneficial to the efficient operation of the system. The boiler connections for external controls are 12V DC and so only controls of 12V DC that have voltage free contacts should be used. (page 25).

ARISTON supply a range of wired and wireless system controls. Contact your supplier for more details.

#### Location

The boiler can be installed on any suitable internal wall (suitable sound proofing may be required when installing onto a stud partition wall). Provision must be made to allow for the correct routing of the flue and siting of the terminal to allow the safe and efficient removal of the flue products. A compartment or cupboard may be used provided that it has been built or modified for this purpose. It is not necessary to provide permanent ventilation for cooling purposes. Detailed recommendations are given in BS 5440 Part 2. If it is proposed that it is to be installed in a timber framed building then reference should be made to IGEM Document, IGE/UP/7 or advice sought from Gas Safe.

Where a room sealed appliance is installed in a room containing a bath or shower, the appliance and any electrical switch or appliance control, utilising mains electricity should be situated specifically in accordance with current IEE Wiring Regulations.

For unusual locations, special procedures may be necessary. **BS 6798** gives detailed guidance on this aspect.

#### Codensate Discharge

The condensate discharge hose from the boiler must have a continuous fall of  $2.5^{\circ}$  and must be inserted by at least 50mm into a suitable acid resistant pipe - e.g. plastic waste or



### **INSTALLATION**


overflow pipe. The condensate discharge pipe must have a minimum diameter of 22mm, must have a continuous fall and preferably be installed and terminated to prevent freezing. The discharge pipe must be terminated in a suitable position:


- Connecting into an internal soil stack (at least 450mm above the invert of the stack). A trap giving a water seal of at least 75mm must be incorporated into the pipe run, there also must be an air beak upstream of the trap.
- ii) Connecting into the waste system of the building such as a washing maching or sink trap. The connection must be upstream of the washing machine/sink. If the connection is downstream of the waste trap then an additional trap giving a minimum water seal of 75mm and an air break must be incorporated in the pipe run, as above.
- iii) Terminating into a gully, below the grid level but above the water level
- iv) Into a soakaway

Note: If any condensate pipework is to be installed externally then it should be kept to a minimum and be insulated with a waterproof insulation and have a continuous fall. The total length of external pipe used should not exceed 3 metres.


Some examples of the type of condensate terminations can be found below.


1. Internal termination of condensate drainage pipe to internal stack.






3. External termination of condensate drainage pipe via internal discharge branch (e.g. sink waste - proprietary fitting).







#### **Condensate Discharge**

Push fit the flexible condensate pipe into the outlet spigot on the appliance. Cut to length and locate outlet into a tundish 4. External termination of condensate drainage pipe via condensate siphon







Connections view behind boiler.

#### Installing the Boiler

Please check that you are familiar with the installation requirement before commencing work (pages 10 - 14).

The installation accessories described in the following list are included in the boiler packaging:

- Hanging bracket
- A paper template (showing the dimensions of the boiler with 5 mm side clearances)
- Connection valves (compression)
- Screws and washers
- Filling loop
- Installation, Servicing and User manual

#### Method of positioning the boiler on the wall

The paper template can be used to ensure the correct positioning of kitchen cabinets etc.

The paper template has to be fixed to the wall and used to locate the position of the hanging bracket and the centre for the flue hole.

Drill and plug the wall and secure the hanging bracket using the screws provided ensure the hanging bracket is level. Remove the boiler from its packaging and remove the front casing panel. Place the boiler on the hanging bracket.

#### NOTE: THE APPLIANCE MUST NOT BE FITTED ON A COMBUSTIBLE WALL SURFACE.

#### Connecting the boiler to the system

- Remove the boiler casing as described on page 14
- Remove the caps and connect the valves to the boiler using the washers provided
- 5 x fibre washers for the CH flow and return, cold water inlet, gas and hot water outlet connections

#### Safety Valve Discharge

The pressure relief valve pipe is made of copper. It should terminate below the boiler safely outside the premises. Care should be taken that it does not terminate over an entrance or window or where a discharge of heated water could endanger occupants or passers by.



## WARNING! DO NOT APPLY HEAT TO THE COPPER SAFETY VALVE OUTLET PIPE WHILST IT IS CONNECTED TO THE 3 BAR SAFETY RELIEF VALVE.

Fill the central heating and DHW system and bleed air from the system as described in the Commissioning instructions (page 27).

The system should be carefully checked for leaks, as frequent refilling could cause premature system corrosion or unnecessary scaling of the heat exchanger. The pipe from the trap should be connected to a drain as described in the relevant regulations.

Pay special attention not to bend the condensate silicone drain pipe is such a way as to interrupt the flow. Please only use drain pipe material compatible with condensate products (refer to BS 6798:2009).

The condensate flow can reach **2 litres/hour** because of the acidity of the condensate products (Ph close to 2), take care before operation.

See page 13 for condensate discharge options.



#### **Gas connection**

Make sure, using the labels on the packaging and the data plate on the appliance itself, that the boiler is in the correct country and that the gas category for which the boiler was designed corresponds to one of the categories available in the country where it will be used.

The gas supply piping must be created and measured out in compliance with specific legal requirements and in accordance with the maximum power of the boiler.

Check that the supplied gas corresponds to the type of gas for which the boiler was designed (see the data plate located on the appliance itself).


It is also important to check that the pressure of the gas (methane or LPG) you will be using to feed the boiler is suitable, because if it is insufficient the power may be reduced, causing inconvenience for the user.

#### Water connection

The illustration below shows the connections for the water and gas attachments of the boiler. See valves configuration on page 13.

Check that the maximum water mains pressure does not exceed 6 bar; if it does, a pressure reducing valve must be installed.

For the measuring of the pipes and of the heating bodies in the heating system, the residual head value should be calculated as a function of the requested flow rate, in accordance with the values shown in the circulation pump graph.




Legend:


- A. Central heating Flow
- B. Domestic Hot Water Outlet
- C. Gas Inlet
- D. Domestic Cold Water Inlet
- E. Central Heating Return
- F. Safety Valve Discharge
- H. Drain Valve
- I. Condensate discharge

## Instructions for removing the housing and inspecting the appliance.

Before carrying out any work on the boiler, switch off the power supply using the external bipolar switch and close the gas tap. To access the inside of the boiler:


- unscrew the two screws from the front panel (**a**), pull the panel forwards and uncouple it from the upper pins (**b**),
- pivot the electronic unit by pulling it forwards (c).







## CAUTION!! REMOVE ONLY THE SCREWS SHOWN IN THE PICTURE

(b)








To calculate the size of the heating installation, refer to the "Available pressure" graph below.

Graph representing the available circulation pump pressure  $\label{eq:constraint} \Delta \text{T20}{}^\circ\text{C}$ 



#### **Underfloor heating**

For appliances with underfloor heating, it is possible but not necessary to fit a safety thermostat onto the underfloor heating outlet. For the electrical connection of the thermostat see the section on "Electrical connections - pages 26".

If the outlet temperature is too high, the boiler will stop both domestic hot water and the heating production and the error code 1 16 "floor thermostat contact open" will appear on the display. The boiler will restart when the thermostat is closed during automatic resetting.

If the thermostat cannot be installed, the underfloor heating equipment must be protected by a thermostatic valve, or by a bypass to prevent the floor from reaching too high a temperature.

## **INSTALLATION**


## BEFORE THE DEVICE IS USED, FOR THE FIRST TIME THE TRAP MUST BE FILLED A WITH WATER.

The siphon is filled with water during deaeration procedure of the boiler (or heating system) - see p. 32


Ensure that the siphon contains water; if not, it must be refilled. Open the manual air vent (2) on the main exchanger until complete filling. Check again the system pressure on the pressure gauge.

## WARNING!

INSUFFICIENT WATER IN THE TRAP CAN TEMPORARILY CAUSE THE FLUE GAS TO BE EXPELLED INTO THE SURROUNDING AMBIENT AIR



#### Water circuit diagram



- 1. Air relief valve
- 3. Main Heat Exchanger
- 4. Detection/Ignition electrode
- 5. Central Heating Return Temperature Probe
- 6. Central Heating Flow Temperature Probe
- 7. Gas Valve
- 8. Secondary Exchanger
- 9. Safety valve
- 10. Automatic By-pass
- 11. Drain valve
- 12. Condensate Trap
- 13. Filling loop
- 14. Central Heating Filter
- 15. D.H.W. Flow Switch
- 16. Diverter valve
- 17. Pressure Gauge
- 18. Water pressure sensor
- 19. Modulating Circulation Pump with air release valve
- 20. Expansion Vessel
- 21. Modulating Fan

### **Connecting the Flue**

Flue System

The provision for satisfactory flue termination must be made as described in BS 5440-1.

The appliance must be installed so that the flue terminal is exposed to outdoor air.

The terminal must not discharge into another room or space such as an outhouse or lean-to.

It is important that the position of the terminal allows a free passage of air across it at all times.


The terminal should be located with due regard for the damage or discolouration that might occur on buildings in the vicinity, it must also be located in a place not likely to cause nuisance.

In cold or humid weather water vapour may condense on leaving the flue terminal.

The effect of such "steaming" must be considered.

If the terminal is less than 2 metres above a balcony, above ground or above a flat roof to which people have access, then a suitable stainless steel terminal guard must be fitted.


The minimum acceptable spacing from the terminal to obstructions and ventilation openings are specified in Fig. 1.



## Fig. 1

- A Directly below an opening, window, etc	300 mm
- B Horizontally to an opening, window, etc	300 mm

- C Below gutters, soils pipes or drain pipes75 mm- D Below eaves200 mm
- E From vertical drain pipe or soil pipe 75 mm
- F From internal or external corner 300 mm
- G Above ground, roof or balcony level 300 mm
- H From a surface facing the terminal 600 mm
- I From a terminal facing a terminal 1200 mm
- J Vertically from a terminal on the same wall 1500 mm
- K Horizontally from an terminal on the same wall 300 mm
- L Fixed by vertical flue terminal



#### Warning


The exhaust gas ducts must not be in contact with or close to inflammable material and must not pass through building structures or walls made of inflammable material.

When replacing an old appliance, the flue system must be changed.

#### Important

Ensure that the flue is not blocked.

Ensure that the flue is supported and assembled in accordance with these instructions.



#### Fitting the Coaxial Flue (Ø 60 / 100 Horizontal)

Contents: 1x Silicone O-Ring (60mm) 1x Elbow (90°) 2x Wall Seals (Internal & External) 1x Flue Pipe including Terminal (1 metre - 60/100) 2x Flue Clamps 4x Screws 2x Seals

Once the boiler has been positioned on the wall, fit the rubber flue seal into the internal flue turret (see diagram opposite),

Insert the elbow into the socket and rotate to the required position. note: It is possible to rotate the elbow 360° on its vertical axis.

Using the flue clamp, seals and screws supplied (Fig 4) secure the elbow to the boiler.

The 1 metre horizontal flue kit (3318073) supplied is suitable for an exact X dimension of 753mm.

Measure the distance from the face of the external wall to the face of the flue elbow (X - Fig 2), this figure must now be subtracted from 753mm, you now have the total amount to be cut from the plain end of the flue. **Note:** A Plume management kit is available for 60/100 horizontal termination. Instructions for installation are supplied with the Plume management kit.

Draw a circle around the outer flue and cut the flue to the required length taking care not to cut the inner flue, next cut the inner flue ensuring that the length between the inner and outer flue is maintained. (Fig 4).

e.g.

#### X = 555mm


753-555 = 198mm (Length to be cut from the plain end of the flue).

Once cut to the required length, ensure that the flue is free from burrs and reassemble the flue. If fitting the flue from inside of the building attach the outer wall seal to the flue terminal and push the flue through the hole, once the wall seal has passed through the hole, pull the flue back until the seal is flush with the wall. Alternatively, the flue can be installed from outside of the building, the outer seal being fitted last.

Should the flue require extending, the flue connections are push fit, however, one flue bracket should be used to secure each metre of flue.


Note: See table for maximum and minimum flue runs.


## **INSTALLATION**



### Fitting the 5" Flue

(Ø 80 / 125 Horizontal/vertical)






Once the boiler has been positioned on the wall, it is necessary to insert the Ø80/125 adaptor (Fig. 5) for both horizontal and vertical flue runs into the boiler flue socket (not supplied with flue kit - Part No 3318095).


Push the adaptor onto the boilers flue connection, grease the seals then add extensions or elbows as required, secure the adaptor, using the clamp and screws provided.


To fit extensions or elbows it is first necessary to ensure that the lip seal is fitted correctly into the inner flue, once verified, it is simply necessary to push them together, no clamps are necessary to secure the flue components.

Before proceeding to fit the flue, ensure that the maximum flue length has not been exceeded (See the tables) and that all elbows and bends have been taken into consideration, for each additional 90° elbow 1 metre must be subtracted from the total flue length, and for each 45° 0.5 metres must be subtracted from the total flue length (the height of the vertical adaptor and a 45° bend can be seen in Fig.6 and a 90° bend in Fig. 7).

Note: DO NOT cut the vertical flue kit.







Note: See table for maximum and minimum flue runs.

Contents: 1x Conical Adaptor (60/100mm) 1x Vertical Flue Kit (80/125mm)

The vertical flue kit is supplied with a specially designed weather proof terminal fitted, it can be used either with a flat roof or a pitched roof.

The Vertical flue kits useable lengths with the pitched roof flashings are indicated in Fig. 7.

Before proceeding to fit the flue, ensure that the maximum flue length has not been exceeded (See the tables) and that all elbows and bends have been taken into consideration, for each additional 90° elbow 1 metre must be subtracted from the total flue length, and for each 45° 0.5 metres must be subtracted from the total flue length (the height of the vertical adaptor and a 45° bend can be seen in Fig. 8).

Mark the position of the flue hole in the ceiling and/or roof (see Fig. 7 for distance from wall to the centre of the flue).

Cut a 130mm diameter hole through the ceiling and/or roof and fit the flashing plate to the roof.

DO NOT cut the vertical flue kit.

To connect the vertical flue kit directly to the boiler, place the vertical starter kit (Part No. 3318079) (see Fig. 7) onto the exhaust manifold and secure with the clamp, fit the vertical adaptor onto the vertical starter kit (note: there is no need to use a clamp to secure this as it is a push fit connection), the vertical flue kit must then be inserted through the roof flashing, this will ensure that the correct clearance above the roof is provided as the terminal is a fixed height.

Should extensions be required, they are available in 1 metre (Part No. 3318077), 500mm (Part No. 3318078) and they must be connected directly to the vertical starter kit before connecting the adaptor to allow the vertical flue kit to be fitted. In the event that extension pieces need to be shortened, they must only be cut at the male end and it must be ensured that the inner and outer flue remain flush.

When utilising the vertical flue system, action must be taken to ensure that the flue is supported adequately to prevent the weight being transferred to the appliance flue connection by using 1 flue bracket per extension.

When the flue passes through a ceiling or wooden floor, there must be an air gap of 25mm between any part of the flue system and any combustible material. The use of a ceiling plate will facilitate this. Also when the flue passes from one room to another a fire stop must be fitted to prevent the passage of smoke or fire, irrespective of the structural material through which the flue passes.

#### INSTALLATION

#### Fitting the Twin Pipe (Ø80 / 80)



Note: See table for maximum and minimum flue runs.

Where it is not possible to terminate the flue within the distance permitted for coaxial flues, the twin flue pipe can be used by fitting a special adaptor to the flue connector and using the aperture for the air intake located on top of the combustion chamber.

Always ensure that the flue is adequately supported, using one flue bracket per extension and avoiding low points. (ARISTON supply suitable clamps as Part No. 3318015). To utilise the air intake it is necessary to:

1) Remove the top of the air intake by cutting it with a suitable knife.

2) Insert the header on the tube or the elbow up until the lower stop (you do not have to use the washer).

3) Insert the elbow/header in the boiler air intake hole and fasten it with screws.

The twin flue pipes can be fitted with or without additional elbows and need no clamps, simply ensure that the lip seal is inserted in the female end of the flue pipe and push the extension piece fully into the previous section of flue pipe or elbow, check that the lip seal is not dislodged when assembling the flue (greasing the seal will aid assembly).

Twin pipe can also be converted back to Coaxial flue to enable vertical termination with a coaxial kit by using the pipe bridge (Twin - Coaxial Adaptor - Part No. 3318089). When running the twin flue pipe vertically.


It is not possible to terminate concentrically horizontally. Termination is only possible with separate air and exhaust terminals. When siting the twin flue pipe, the air intake and exhaust terminals must terminate on the same wall, the centres of the terminals must be a minimum of 280 mm apart and the air intake must not be sited above the exhaust terminal (refer to Fig. 10). The air intake pipe can be run horizontally, however, the terminal and the final 1 metre of flue must be installed either horizontally or with a slight fall away from the boiler to avoid rain ingress.

It is also strongly recommended that the air intake pipe run be constructed of insulated pipe to prevent condense forming on the outside of the tube.

Ensure the exhaust tube has a minimum fall back to the boiler of 1° / metre (1° = 17.5mm/metre)

The maximum permissible flue length for twin flue is dependent on the type of run used (see table on page 23).

For further information relating to flue runs not illustrated, please contact the **Technical Department** on **0333 240 7777.** 



For coaxial systems, the maximum development value, mentioned in the table below also takes into account an elbow. For twin flue systems the maximum development value, mentioned in the table includes the exhaust gas/air intake terminal.

Twin flue systems outlets should respect the following instructions:

- 1- Use the same ø 80 mm flue pipes for the air intakes and exhaust gas ducts.
- 2- If you need to insert elbows in the air intake and exhaust gas ducts, you should consider for each one the equivalent length to be included in the calculation of developed length.
- 3- The exhaust gas duct should jut above the roof by at least 0.5 m.
- 4- The intake and exhaust gas ducts in Type C13 + C53 must be installed on the same wall, or where the exhaust is vertical and the air intake horizontal, the terminals must be on the same side of the building.





Table of flue gas exhaust duct lengths

		Maximum Extension Exhaust-air (m) ALTEAS ONE NET		Diameter of pipe	
FLUE	TYPE			(mm)	
		30	35		
System	C13 C33 C43	7	6	ø 60/100	
Coaxial System	C13 C33 C43	20	24	ø 80/125	
c		S1 = S2			
sten	C13	30 = 30	23 = 23	a 90/90	
e Sy	C33	40 = 40	30 = 30	ø 80/80	
pipe	C43	30=30	23 = 23		
Twin-pipe System	C53	S1 + S2			
F	033	60	45	ø 80/80	

S1 = Air intake S2 = Flue gas exhaust

S1 = S2 - Air intake and flue gas exhaust equal lengths S1 + S2 - Air intake and flue gas exhaust unequal lengths



/23 ARISTON

## WARNING!

BEFORE PERFORMING ANY WORK ON THE BOILER, FIRST DISCONNECT IT FROM THE ELECTRICAL POWER SUPPLY USING THE EXTERNAL BIPOLAR SWITCH AND REMOVE THE FUSE.

#### **Electrical connections**

For increased safety, ask a qualified technician to perform a thorough check of the electrical system.

The manufacturer is not responsible for any damage caused by the lack of a suitable earthing system or by the malfunctioning of the electricity mains supply.


Make sure that the system is able to withstand the maximum power absorbed by the boiler (this is indicated on the appliance data plate). Check that the section of the wires is suitable and is not less 0,75 mm<sup>2</sup>

The appliance must be connected to an efficient earthing system if it is to operate correctly.

The power supply cable must be connected to a 230V-50Hz network, where the L-N poles and the earth connection are all respected.

#### Important!

In the event that the power supply cable must be changed, replace it with one with the same specifications.



## Power supply cable

Important!

The appliance is supplied with a fly-lead already connected, this must be connected to a 240V supply fused at 3 Amp and must facilitate completed electrical isolation of the appliance, by use of a fused double pole isolator having a contact separation of at least 3mm in all poles or alternatively by means of a 3A fused three pin plug and unswitched shuttered socket outlet both complying with BS1363.


The use of multiplugs, extension leads or adaptors is strictly prohibited.

It is strictly forbidden to use the piping from the hydraulic, heating and gas systems for the appliance earthing connection. The boiler is not protected against the effects caused by lightning. If the mains fuses need to be replaced, use 2A rapid fuses.

#### **Peripheral unit connection**

To access peripheral unit connections carry out the following steps:

- Disconnect the boiler from the power supply
- Remove the casing
- Rotate the control panel while pulling it forwards
- Unhook the two clips to have access to the peripherical connections and the main P.C.B.



Peripheral connections:


**BUS** = Remote control connection

FLOOR/TA2 = the underfloor heating thermostat or the room thermostat 2 (selected via parameter 223)

**SE** = the external sensor.

**SOL** = Solar temperature probe

**TA1** = the room thermostat 1



#### Cube Room sensor (wireless) Connection

To connect a room thermostat, read the instructions present in the kit delivered with the gas boiler.

DO NOT CONNECT 240V TO ANY PERIPHERAL CONNECTIONS


#### Room Thermostat / Remote Clock Connection

To connect a room thermostat, it is necessary to:

1. Open the control panel

- 2. Loosen the cable clamp using a screwdriver and insert the wires leading from the room thermostat
- 3. Connect the wires to the terminals as indicated in the figure below, removing the link
- 4. If a remote time clock is to be fitted, using a volt free switching time clock connect the switching wires from the time clock following points 1 3 above
- 5. If using an external time clock and room thermostat, these must be connected in series as shown in diagram C,
- 6. Ensure that they are well connected and not subject to stress when the control panel is closed

#### DO NOT CONNECT 240V TO ANY PERIPHERAL CONNECTIONS




Timeclock and Room Thermostat low voltage compatible

#### **Electrical diagram**

For increased safety, ask a qualified technician to perform a thorough check of the electrical system.

The manufacturer is not responsible for any damage caused by the lack of a suitable earthing system or by the malfunctioning of the electricity mains supply.



#### **Initial preparation**

Ariston Thermo UK Ltd support the benchmark initiative.

On pages 77 and 78 of this manual the Benchmark Commissioning Checklist and Service interval Record can be found. It is important that this is completed in the presence of your customer, they are shown how to use it, and it is signed by them. Please instruct your customer that they must have this manual with them whenever they contact a service engineer or us.

Preliminary electrical system checks to ensure electrical safety must be carried out by a competent person i.e. polarity, earth continuity, resistance to earth and short circuit.

#### **Electricity supply**

- Check that the voltage and frequency of the electricity supply correspond to the data shown on the boiler data plate;
- Make sure that the earthing connection is efficient.

#### Filling the Heating System:

#### ATTENTION!!

#### CONNECT THE PIPE OF CONDENSATE DISCHARGE BEFORE REFILLING AND THE DE-AERATION OF THE HEATING CIRCUIT.

Remove the front casing panel and lower the control panel as described on page 14.

Open the central heating flow and return cocks supplied with the connection kit;

Open the manual air vent positioned at the side of the primary exchanger **(2)**. The valve is already connected to a discharge pipe related to the condensate trap.

Close all air release valves on the central heating system; Gradually open the valves at the filling point (filling loop) until water is heard to flow, do not open fully;

Open each air release tap starting with the lowest point and close them only when clear water free of air is visible;

Continue filling the system until at least 1.5 bar registers on the pressure gauge;

Inspect the system for water tightness and remedy any leaks discovered.

#### IMPORTANT!

MANUALLY VENT THE HEAT EXCHANGER AT THE MANUAL AIR VENT. FAILURE TO VENT ADEQUATELY MAY DAMAGE THE HEAT EXCHANGER (PAGE 8, LEGEND 2).

#### Filling of the DHW System:

Close all hot water draw off taps;

Open the cold water inlet cock supplied with the connection kit; Slowly open each draw off tap and close them only when clear water, free of bubbles, is visible.

#### Gas Supply:

Inspect the entire installation including the gas meter and test for tightness. The entire installation should be in accordance with the relevant standards. In GB this is BS 6891 and in IE this is the current edition of I.S.813.

The connection on the the appliance is a 15mm (22mm on 35Kw) nut and olive located at the rear of the gas service cock.

If the gas supply serves other appliances, ensure that an adequate supply is available both to the boiler and the other appliances when they are in use at the same time.

Pipe work must be of an adequate size. The final pipe size must not be smaller than the appliance inlet size.

Open the gas cock (supplied with the connection kit) to the appliance and check the gas connection on the appliance for leaks.

#### Water Treatment:

guidance;


The boiler is equipped with a stainless steel heat exchanger. The detailed recommendations for water treatment are given in BS 7593 (Treatment of water in domestic hot water central heating systems); the following notes are given for general

If the boiler is installed on an existing system, any unsuitable additives must be removed;

Under no circumstances should the boiler be fired before the system has been thoroughly flushed; the flushing procedure must be in line with BS7593.

Firstly fill the central heating system with the power off, and flush through cold, fill the central heating system again, adding a flushing detergent, run the boiler on central heating until it reaches its operating temperature and flush the system, refill the system with a suitable corrosion inhibitor,

Note: Failure to carry out the flushing procedure will result in the warranty becoming void.



27 🗅 ARISTON

## **FIRST IGNITION OPERATION**

Date		
1. Check the electrical supply.	2. Check the type of gas (change the gas if necessary durung the Calibration procedure point 8).	
Complete	Complete	
3. Check the gas tightness.	4. Check the Flue	5. Fill the installation.
Complete	Complete	Complete
6. Check the hydraulic water tightness.	7. Measure the gas inlet static pressure.	
Complete	Complete	
8. Carry out the deaeration cycle a necessary). Adjusting the CO2 by	· · · · ·	
Complete		

9. Set the heating power.	10. Balance the central heating circuit.	11. Check the operation in DHW mode.
Complete	Complete	Complete
12. Adjust DHW flow rate on the boiler (if necessary).	13. Check gas rate.	14. Check the ionisation current.
Complete	Complete	Complete
15. Explain to the end user the working of the boiler.		
Complete		

#### Start-up procedure

Press the ON/OFF button on the control panel to switch on the boiler: the display will light up.

The initialisation procedure - indicated by the bar - begins.



Once the procedure is completed, the display will visualise the temperatures set for the central heating and domestic hot water circuits (display configuration: boiler base).



The boiler will request the setting of the date, time and language. Proceed as indicated in the USER MENU - see the User's Manual.

#### **FIRST IGNITION**

## CARRY OUT THE DEAERATION CYCLE AND AUTOMATIC CALIBRATION

#### 1. Assicurarsi che:

- The gas valve is closed;
- The electrical connection has been properly carried out. Make sure that, in any case, the green/yellow earthing wire is connected to an efficient earthing system;
- Unscrew the cap on the automatic air relief valve;
- The exhaust duct for combustion products should be suitable and free from any obstructions;

IMPORTANT! DURING THE CALIBRATION PROCEDURE AND MEASUREMENT OF THE CO2 VALUE, IT'S IMPORTANT THAT THE BOILER WORKS WITH THE FRONT COVER CLOSED AND THE AIR/ FUMES DUCTS FULLY ASSEMBLED.


- Any necessary ventilation inlets in the room should be open (type B installation).
- Check whether the condense trap contains water; if not, it must be refilled. If necessary, open the manual air vent on the main exchanger until complete filling.

N.B.: if the boiler will not be used for long periods, the trap should be filled before the boiler is started up again. It is dangerous not to refill the siphon as fumes may be released into the environment.

#### 2. Supply static pressure check

Loosen the screw 1 and insert the pressure gauge connection pipe into the pipe tap.

The supply pressure should correspond to the value established in relation to the type of gas, for which the boiler is designed see **Table summarising changes**.




## ATTENTION!! THE BOILER CAN NOT BE ACTIVATED IF THE PRESSURE IS NOT CORRESPONDING TO THE TABLE SUMMARISING CHANGES.

#### 3. ACTIVATION OF THE DISAERATION PROCEDURE AND AUTOMATIC CALIBRATION

• Switch on the boiler (by pressing the ON/OFF button) and use the Mode button to select the standby mode, where no

hot water or heating requests are made. The display asks to start the deaeration and calibration procedure.



 Press the OK button. The display shows:

> "Attention, this procedure can be performed only by qualified personnel. To proceed, press OK button for 5 seconds."

• Press OK for 5 seconds. The display shows:

"System air purge The function activates the air-purge cycle of system. To start the cycle, press "OK" button (advised) otherwise "ESC"."

• Press the OK button. The boiler will start a deaeration cycle lasting about 7 minutes (See below). If you need to stop it press MODE. During the



deaeration cycle open the manual air vent (2) on the heat exchanger and close when clear water free of air is visible. At the end, check that the system is completely deaerated and, if not, repeat the procedure.

The display shows:

#### "If air is still present inside the system, start again the air purge cycle (OK button); otherwise press the exit button (ESC button)"

• Verify that the system pressure is at least 1 bar on the pressure gauge. Open the filling valve if pressure is not sufficient and close as soon as it reaches 1 - 1.5 bar

Note! If pressure in the heating circuit decreases, the display shows Malfunction warning 1P4 (parameter 241 alert pressure).

If the pressure falls below the alarm value the display will show the Error 108. Open the filling valve and close as

soon as it reaches 1 - 1.5 bar IN THESE CASES,


THE PROCEDURE **IS INTERRUPTED.** AFTER FILLING THE SYSTEM THE DISPLAY **REQUESTS TO START** AGAIN THE SYSTEM AIR PURGE AND AUTOMATIC CALIBRATION .





• After the system air purge the display shows the gas set from factory. Enter the type of gas used (if necessary), press the button  $\checkmark$  to select: 0 = Natural gas (factory setting) 1 = LPG 2 = G230 (IT)

3 = G130 (FR)




Press OK. The display shows: "Automatic Calibration This function enables the boiler to calibrate automatically. This procedure may take a few minutes. If you want to proceed press OK."

 Press OK to enable the Automatic Calibration.




The procedure may take few minutes. The display shows the steps of the procedure




If the calibration is completed the display shows "Completed Calibration" and returns to the main screen:



• Start the boiler by selecting the heating or domestic hot water operation using the Mode button.



**IF AN ERROR IS STILL REPORTED, CONTACT A QUALIFIED TECHNICIAN.** 




#### WARNING!!

THE AUTOMATIC CALIBRATION MUST BE DONE IN CASE OF:

- REPLACEMENT OF: FAN, GAS VALVE, AIR/GAS MIXER, BURNER, ELECTRODE.
- REPLACEMENT OF P.C.B.
- GAS CHANGEOVER
- ANY MODIFICATION TO THE FOLLOWING PARAMETERS 220 - SOFT IGNITION 231 - MAX CH ADJUSTABLE 232 - MAX DHW PERCENTAGE 233 - MIN PERCENTAGE 234 - MAX CH PERCENTAGE

#### 4. Preparing the measuring equipment

Connect the calibrated measuring device to the left-hand combustion outlet by unscrewing the screw and removing the blanking cover.



### 5. Supply dinamic pressure check

Loosen the screw **1** and insert the pressure gauge connection pipe into the pipe tap. Switch the boiler on at D.H.W. maximum power, enabling the "Chimney function" (press the RESET button for 10 seconds and press th button > to select D.H.W. maximum power).

The supply pressure should correspond to the value established in relation to the type of gas, for which the boiler is designed see Table summarising changes.



## ATTENTION!! THE BOILER CAN NOT BE ACTIVATED IF THE PRESSURE IS NOT CORRESPONDING TO THE TABLE SUMMARISING CHANGES



## 6. Adjusting the CO2

#### **Intermediate Power**

Draw off the domestic hot water at the maximum water flow rate. Select the Chimney function by pressing the RESET button for 10 seconds.

WARNING! When the cleaning function is activated, the temperature of the water coming out of the boiler may be more than 65°C.

The display will visualise the Chimney Function active at Intermediate Power



Wait 1 minute for the boiler to stabilise before carrying out the combustion analyses.

Read the CO<sub>2</sub> value (%) and compare it with the values given in the table A below:

Table A				
	ALTEAS ONE NET 30/35			
	CO2 (%)			
Gas	Intermediate	Max Power	Min	
	Power	DHW	Power	
G20	8,8 ± 0,7			
G30 / G31	10,5 ± 1,0			

## N.B.: VALUES WITH THE CASING CLOSED.

If the  $CO_2$  (%) value is correct proceed to the next operation.

f the value of CO<sub>2</sub> detected, differs from the values given in the table, press the button **OK**. The display, after a few seconds, shows an adjustment bar. Press the buttons b



 $\checkmark$  to adjust the value. It's possible

modify the value of  $\pm$  0,5%. Press **OK** to confirm and proceed to the next operation.

#### Maximum power DHW

Press the button > to select Max Power DHW The display will visualise the Chimney Function active at the Maximum power DHW

Chimney active	
Intermediate Power	
Max power DHW	
Max power CH	

Wait 1 minute for the boiler to

stabilise before carrying out the combustion analyses.

Read the CO<sub>2</sub> value (%) and compare it with the values given in the table A.

If the CO<sub>2</sub> (%) value is correct proceed to the next operation.

If the value of CO<sub>2</sub> detected, differs from the values given in the table, press the button **OK**. The display, after a few seconds, shows an adjustment bar. Press the buttons b



 $\checkmark$  to adjust the value. It's possible modify the value of ± 0,5%. Press **OK** to confirm and proceed to the next operation.

#### Minimum power

Press the button > to select Minimum power The display will visualise the Chimney Function active at Minimum power



Wait 1 minute for the boiler to stabilise before carrying out the combustion analyses.

Read the CO<sub>2</sub> value (%) and compare it with the values given in the table A.

If the CO2 (%) value is correct proceed to the next operation.

f the value of CO<sub>2</sub> detected, differs from the values given in the table, press the button **OK**. The display, after a few seconds, shows an adjustment bar. Press the buttons  $b \checkmark b$  to adjust



the value. It's possible modify the value of  $\pm$  0,5%. Press OK to confirm and proceed to the next operation.

#### 7. Ending the adjustment

Exit cleaning mode by pressing RESET. Stop the draw-off. Verify and repair any leaks of gas. Refit the blanking cover for the combustion outlets.

## THE CLEANING FUNCTION IS AUTOMATICALLY DEACTIVATED AFTER 30 MINUTES OR MANUALLY BY BRIEFLY PRESSING THE RESET BUTTON.

#### **Maximun Heating Power adjustment**

The maximum heating power can be adjusted to between the maximum power allowed by the boiler and the minimum power). The display shows the value between "100" and 0 of this interval. To check the maximum heating power, access menu 2/sub menu 3/parameter 1, check the value and, if necessary, modify it as indicated in the Gas Pressure table.

#### Checking slow ignition power

The soft light can be adjusted between the maximum power and the minimum power.

The display shows the value between "100" and 0 of this interval. To check the slow ignition power, access menu 2/sub menu 2/ parameter 0.

If needed, change the parameter value until suitable pressure is achieved.


#### Heating ignition delay adjustment

This parameter – menu 2/sub menu 3/parameter 5 - can be used to manually (0) or automatically (1) set the delay time before the subsequent reignition of the burner after it has switched off on reaching the desired temperature.

By selecting manual, it is possible to set the delay in minutes using the successive parameter (menu 2/sub menu 3/parameter 6), to a time between 0 and 7 minutes.

Automatic selection means that the boiler will establish the delay time based on the set-point temperature.

The table indicate the existing relationship between the gas pressure at the burner and the boiler power level in heating mode.



## Table summarising changes

		eter		ALTEAS ONE NET						
		parameter			30			35		
		pa	G20	G30	G31	G20	G30	G31		
Lower Wobbe index (15°C, 1013 mbar) ( MJ/m <sup>3</sup> )			45,67	80,58	70,69	45,67	80,58	70,69		
Supply gas pressure min-max (mbar)			17-25	25-35	25-45	17-25	25-35	25-45		
Slow ignition		220	42 43							
Maximum C. H.power Adjustable		231	65 65							
Minimum power (%)		233	1 1							
Max CH power (%)		234	82			73				
Max DHW power (%)		232	88			84				
Parametro 202 - Set gas type			0	1	1	0	1	1		
Gas flow max/min (15°C, 1013 mbar) (nat - m3/h) (GPL - kg/h)	max D.H.W		3.17	2.37	2.33	3.65	2.72	2.68		
	max C.H		2.96	2.21	2.18	3.28	2.44	2.41		
	min			0.24	0.23	0.37	0.28	0.27		

#### **Gas Changeover**

The boiler is factory setted for the gas type indicated on the data plate. The adjustment, if necessary, must be performed by a Qualified Technician. It is not necessary a conversion kit, because the boiler has a auto adaptation gas system. Proceed as indicated:

- 1. Change parameter 202 to the new gas (see Technical Area). The display shows the error "The boiler must be calibrated".
- 2. Perform the Calibration procedure and check the CO<sub>2</sub> as indicated at the page 30.
- 3. At the end apply, near the data plate, the new label (supplied with the product) indicated the new gas type used.
- 4. Verify and repair any leaks of gas.

## Set for gas: / Regolata per funzionare a gas: / Réglé pour gaz: / Gerelged voor gas: / Reglaje para gas: / Ajustamento a gás : / Seta pentru gaz: / Набор для газа / Ρύθμιση για το φυσικό αέριο: / Set za plin:


G20 20 mbar G230 20 mbar	
G30 - G31 28/37 mbar	

Example: Boiler adjusted for LPG

#### WARNING!!

THE AUTOMATIC CALIBRATION MUST BE DONE IN CASE OF:

- REPLACEMENT OF: FAN, GAS VALVE, AIR/GAS MIXER, BURNER, ELECTRODE.
- REPLACEMENT OF P.C.B.
- GAS CHANGEOVER
- ANY MODIFICATION TO THE FOLLOWING PARAMETERS
  - 220 SOFT IGNITION
  - 231 MAX CH ADJUSTABLE
  - 232 MAX DHW PERCENTAGE
  - 233 MIN PERCENTAGE
  - 234 MAX CH PERCENTAGE



## COMMISSIONING

#### **AUTO** function

This is a function which enables the boiler to automatically adapt its operation routine (the temperature of the heating elements) in line with the outdoor conditions, in order to achieve and maintain the requested room temperature conditions.

Depending on the peripheral units connected and the number of zones controlled, the boiler adjusts its flow temperature automatically.

The various corresponding parameters should therefore be set (see adjustments menu).

To activate the function, press the Auto button.

#### Example 1:

Single zone system (high-temperature) with on/off room Thermostat:

In this case the following parameters must be set:

- 4 21 Activation of temperature adjustment using sensors
  - Select 1 = Basic temperature adjustment
- 2 44 Boost Time (optional)

The wait time for the flow temperature increase in steps of 4°C may be set. The value varies according to the type of system and installation.

If the Boost Time value = 00 the function is not activated.

#### Example 2:

Single zone system (high-temperature) with on/off room Thermostat + outdoor sensor:

- In this case the following parameters must be set:
- 4 21 Activation of temperature adjustment using sensors
- Select 3 = outdoor sensor only
- 4 22 Temperature adjustment curve selection

- Select the relevant curve according to the type of system, installation, heat insulation used in the building, etc.

4 23 - Perform a parallel curve shift if necessary, increasing or decreasing the set-point temperature (this may also be modified by the user, using the heating temperature adjustment knob, which, with the Auto function activated, is used to shift the curve in a parallel manner).

#### Example 3:

Single zone system (high-temperature) with Sensys controller + outdoor sensor

In this case the following parameters must be set:

- 4 21 Activation of temperature adjustment using sensors
  - select 4 = outdoor sensor + room sensor
- 4 22 Temperature adjustment curve selection
  - Select the relevant curve according to the type of system, installation, heat insulation used in the building, etc
- 4 23 Perform a parallel curve shift if necessary, increasing or decreasing the set-point temperature. (This may also be changed by the user by the buttons 8 which, with the Auto function activated, is used to shift the curve in a parallel manner.)
- 4 24 Influence of room sensor

- used to adjust the influence the room temperature has on the calculation of the set-point flow temperature (20 = maximum, 0 = minimum).

Note: See page 38 for details on accessing menus.



## **BOILER PROTECTION DEVICES**

#### Appliance shut-off conditions

The boiler is protected from malfunctions by means of internal checks performed by the electronic P.C.B., which stops the boiler from operating if necessary. In the event of the boiler being shut off in this manner, a code appears on the control panel display which refers to the type of shut-off and the reason behind it. Two types of shut-off may occur:

#### Safety shut-off

This type of error is "volatile", which means that the boiler starts up again automatically as soon as the problem which caused the shut-off is removed.

The display shows the code and the error description. **"Fault 110** - Send Probe Damaged"



In fact, soon as the cause of the shut-off disappears, the boiler starts up again and continues to operate normally.

If the boiler still indicates a safety shut-off, switch it off. Make sure the external electric switch is in the OFF position, shut off the gas valve and contact a qualified technician.

#### Safety shut-off due to insufficient water pressure

In caso di insufficiente pressione dell'acqua nel circuito riscaldamento la caldaia segnala un arresto di sicurezza. The display shows "**Fault 108** - Filling Needed".



If the re-balancing request is performed on a frequent basis, switch the boiler off, bring the external electric switch to the OFF position, shut off the gas valve and contact a qualified technician to check for any leaks of water.


#### **Operation shutdown**

This type of error is "non-volatile", which means that it is not removed automatically.

The display shows the code and the error description.

To restore normal operation press the **RESET** button on the control panel.

The dispay shows <u>"Reset in progress"</u> and then <u>"Fault solved"</u>. If the problem manifests itself again after several attempts to reset the appliance, contact a qualified technician.



#### Important

If this shutdown occurs frequently, contact an authorised Technical Service Centre for assistance. For safety reasons, the boiler will permit a maximum of 5 resets in 15 minutes (5 presses of the RESET button); at the 6th attempt within this 15-minute period the boiler will shut down and may only be operated again after the electricity supply has been disconnected. If the shutdown is occasional or an isolated event, this is not a problem.

The first figure of the error code (e.g. 1 01) indicates within which operational assembly the error occurred.

- Primary Circuit
- 2 Domestic Hot Water Circuit
- **3** Internal Electronic Part
- 4 External Electronic Part
- ${\bf 5}$  Ignition and Detection
- 6 Air inlet flue gas outlet
- 7 Multizone heating
- 8 Combustion Control System

#### **Malfunction warning**


This warning is shown by the display in the following format: **5 P 3** = Flame cut-off

the first figure indicating the operational assembly is followed by a P (warning) and the code relating to the specific warning.

#### **Circulation pump malfunction signal**

The circulation pump has an LED display that shows its operating status:

LED off: The circulation pump is electrically charged. LED solid green: circulation pump enabled. LED flashing green: change of speed taking place. LED red: Circulation pump is blocked or lacks water.



#### **BOILER PROTECTION DEVICES**

#### Table summarising error codes

Cei	Central Heating circuit RESET							
Dis	play	Description	Х					
1	01	Overheat						
1	02	Pressure Sens Error						
1	03							
1	04							
1	05	Insufficient circulation						
1	06							
1	٢٥							
1	08	Insufficient water (request filling)						
1	10	C.H. Flow temp. probe circuit open / short circuit						
1	12	C.H. Return temp. probe circuit open / shor	t circuit					
1	14	External sensor circuit open / short circuit						
1	18	Heating delevery probe problem						
1	P 1							
1	Ρ2	Insufficient circulation indication						
1	PЗ							
1	РЧ	Insufficient water (request filling)						
D.H	I.W. c	ircuit						
2	05	DHW In Probe Open Circuit						
Inte	ernal	P.C.B.'s						
З	01	EEPROM error						
3	02	Comunication error						
3	03	Main P.C.B. error	Х					
3	04	Too many (> 5) resets in 15 minutes						
3	05	Main P.C.B. error	Х					
3	06	Main P.C.B. error						
3	٦	Main P.C.B. error	Х					
3	13	Low Voltage Fault						
3	Ρ9	Sched.Maintanace-Call Service						
Ext	ernal	P.C.B.'s						
Ч	11	Zone 1 - Room sensor circuit open / short ci	rcuit					
Ч	12	Zone 2 - Room sensor circuit open / short c						
Ч	13	Zone 3 - Room sensor circuit open / short c						
lqn	ition	and Detecion						
5	01	No flame detected (After 5 times with 5P6)	х					
5	02	Flame detected with gas valve closed						
5	03	Flame detected with gas valve closed (After 20 seconds with 502)	Х					
5	04	Flame lift	Х					
5	Р З	Flame cut-off						
5	РS	Low Gas Pressure Fault						
5	P 6	Ignition Failed						
Air	Inlet	/ Flue gas outlet						
б	11	Fan Warning - Anomaly in air inlet and / or f exhaust ducts (Boiler switch off the fan wor minutes at maximum). If the problem is not resolved appears error	ks 20					
6	12	Fan Error (speed higher or lower than the set values)						

Mu	Multi-zone Heating					
٦	01	Zone 1 send sensor defective				
٦	02	Zone 2 send sensor defective				
٦	03	Zone 3 send sensor defective				
٦	11	Zone 1 return sensor defective				
٦	12	Zone 2 return sensor defective				
٦	13	Zone 3 return sensor defective				
٦	55	Zone 2 overheating				
٦	23	Zone 3 overheating				
٦	50	All Heating Zones locked				
Со	mbus	tion Control System (CCS)				
8	01	Calbration Tuning Fault				
8	02	Flame Sensed with Gas Valve Closed				
8	03	Mismatch kW Size, ID combustion (Set parameter 229)				
8	04	Decoupling Clip-In required (see note)				

#### NOTE - ERROR 804:

TO CONNECT THE BOILER TO ELECTRONIC SOLUTIONS FOR SOLAR MANAGEMENT OR IBRID SYSTEMS (ONLY FOR COMBINATIONS NOT ADMITTED), IT'S NECESSARY TO INSTALL A CLIPIN SUPPLIED AS ACCESSORY CODE 3319171.

#### **Anti-frost Device**

The anti-frost function acts on the central heating flow temperature probe, independently from other regulations, when the electrical supply is turned on.

If the primary circuit temperature falls below  $8^\circ\text{C}$  the pump will run for 2 minutes.

After the two minutes of circulation (fixed) the boiler will check the following:

- a) if the central heating flow temperature is > 8°C, the pump stops;
- b) if the central heating flow temperature is between 4 and 8°C, the pump will run for another two minutes;
- c) if the central heating flow temperature is < 4°C, the burner will fire (heating position) at minimum power until the temperature reaches 33°C, the burner will go out and the pump will continue to run for two minutes.

The anti-frost device activates only when (with the boiler operating correctly):

- the system pressure is correct;

- the boiler is electrically powered;

- there is a supply of gas.

#### **TECHNICAL AREA** - reserved for qualified technician


Accessing the **Technical Area** allows for setting/configuring the device according to the specific requirements of every installation procedure.

It also provides important information relating to the efficient operation of the boiler.

The Technical Area comprises various display windows that allow for directly accessing the parameters Intervening in each single product installation/configuration phase.

The parameters relating to each single menu are listed in the following pages.

The various parameters can be accessed and modified using the OK button , the programming Keys **b**  $\checkmark$  and the ESC button  $\backsim$  (see picture below).



For accessing the <u>Technical Area</u> simultaneously press the ESC and OK buttons for 5 seconds; the display will visualise the request for entering the technical code.

Insert code
Insert technical code
222
Save

Press the programming key  ${\bf b} \checkmark {\bf b}$  to select  ${\bf 234}$  and press the OK button .

To move within the Technical Area, press the programming key  $b < \lambda$  and press OK button to access the selected window.

Press the programming key b  $\checkmark$  to select a parameter and press OK button to access it.

To modify the value of a parameter, press the programming key **b**  $\checkmark$  and press OK button to store the value.

Use the ESC  $\bigcirc$  button to exit a parameter without storing the modification and for returning to the normal viewing mode.

Technical area	
Language, date and time	Î
Complete Menu	
Configuration Wizard	
Service	
Faults	

Example:

Modification of parameter

2.3.1 Max. Adjustable Central Heating Power Proceed as follows:

- Simultaneously press the ESC 
   and OK buttons for 5
   seconds; the display will visualise the request for entering the
   technical code.
- 2. Press the programming key **b**  $\langle \rangle$  and select code 234.
- Press the OK button; the display will visualise the available windows.
- 4. Press the programming key b
   **X** to select the Complete Menu.
- Press the OK button to access; the display will visualise the available menus.
- Press the programming key b
   to select Menu 2 Boiler parameters.
- 7. Press the OK button. The display will visualise the available sub-menus.
- Press the programming key b
   to select 2.3 Central heating 1.
- Press the OK button to access.
   The display will visualise the parameters relative to sub-
- menu 2.3. 10. Press the programming key **b**  $\checkmark$  **b** to select parameter 2.3.1 - Max. C.H. Adjustable.
- Press the OK button to access the parameter. The display will visualise the value of the parameter (50%) in addition to the minimum and maximum values allowed.
- Press the programming key b
   to select the new value, e.g. 46%.
- 13. Press the OK button to store the modification.
  (To exit the parameter without storing the modification, press the ESC button).
- 14. Press the ESC 🕤 button to return to the normal viewing mode.




	Menu
0	Network
1	<not available=""></not>
2	Boiler Parameters
3	<not available=""></not>
4	Zone1 Parameters



2.3 Central Heating-1				
2.3.0	Max CH Absolute	62		
2.3.1	Max CH Adjustable	50		
2.3.2	<not available=""></not>			
2.3.3	<not available=""></not>			
2.3.4	<not available=""></not>			





#### COMPLETE MENU STRUCTURE

Tecnical Area
Service code (reserved for qualified technicians) - Press the programming key b 🔨 V to select 234 and press the OK button .
Language, date and time - Follow the instructions of the display.
Press OK button at each entry to save
COMPLETE MENU - The parameters relating to each individual menu are listed in the following pages.
Configuration Wizard
Boiler
Configuration parameters
→ Gas Parameter Direct access to the parameters → 220 - 230 - 231 - 232 - 233 - 234 - 270
→ Settings Direct access to the parameters → 220 - 231 - 223 - 238 - 245 - 246
Visualization
Direct access to the parameters $\rightarrow$ 821 - 822 - 823 - 824 - 825 - 827 - 830 - 831 - 832 - 833 - 840 - 835 - 874
Direct access to the parameters $\rightarrow$ 402 - 502 - 602 - 420 - 520 - 620 - 434 - 534 - 634 - 830
Guided procedures
System Filling
System air purge
Exhaust fumes analysis
Service options
Service Center Data - To insert the name and phone number of Service Center
The data appears in the display in case of error
Enable service warnings
Service warning reset
Months remaining before Service
Test mode
Pump test
3 way valve Test
Fan test
Service
Boiler
Configuration parameters
Gas parameter
Direct access to the parameters $\rightarrow$ 220 - 230 - 231 - 232 - 233 - 234 - 270
Direct access to the parameters → 821 - 822 - 824 - 825 - 827 - 830 - 831 - 832 - 833 - 840 - 835
Boiler PCB change
Direct access to the parameters -> 220 - 226 - 228 - 229 - 231 - 232 - 233 - 234 - 247 - 250 - 253
Automatic Calibration
see page 30
<b>Faults -</b> The display shows the last 10 errors with details of the code, description and date.
Turn the encoder to scroll the errors

menu	sub-menu	parameter	description	value	default setings	
SEF	<b>VIC</b>	EC	CODE			
Pre	ss th	ı pr	ogramming key <b>b</b> to select	code 234 and press	Ок	
co	MPL	ET	E MENU			
0	NE	TW	/ORK			
0.	2	BUS NETWORK				
0.	2.	0	Network Presence	Boiler		
			Indication of the devices cor	nected via BUS.		
0.	4	BC	DILER USER INTERFACE			
0.	4.	0	Zone to be set by display	from 1 to 3 (nr)	1	
0.	4.	1	Backlight timing	from 1 to 10 minutes or 24 hours	10	
0.	4.	2	Thermoregulation button deactivation	0 = OFF 1 = ON	0	
2	BC	DILE	ER PARAMETERS	l	-	
2.	0	GE	ENERAL			
2.	0.	0	DHW Setpoint Temperature	from 36 to 60 (°C)	55	
			Setting by DHW button 2			
2.	0.	1	DHW Pre-Heating	0 = OFF 1 = ON	0	
2.	0.	2	Gas type	0 = Natural Gas 1 = LPG 2 = G230 3 = G130	0	
2.	1	FF	REE PARAMETERS			
2.	1.	4	Boiler circulator type	0 = Standard effi- ciency 1 = High efficiency	1	
			ONLY FOR SERVICE - To t substitution P.C.B.			
2.	2	SE	TTINGS			
2.	2.	0	Soft ignition	from 0 to 100		
			see Table summarising ch	anges		
2.	2.	3	see Table summarising ch Underfloor thermostat or zone 2 ambient thermostat selection	anges 0 = Floor safety thermostat 1 = Zone 2 ambient thermostat	0	
2. 2.	2. 2.	3	Underfloor thermostat or zone 2 ambient thermostat selection Termoregulation	0 = Floor safety thermostat 1 = Zone 2 ambient thermostat 0 = Absent 1 = Present	0	
			Underfloor thermostat or zone 2 ambient thermostat selection	0 = Floor safety thermostat 1 = Zone 2 ambient thermostat 0 = Absent 1 = Present	0	
			Underfloor thermostat or zone 2 ambient thermostat selection Termoregulation <i>Termoregulation can be a</i>	0 = Floor safety thermostat 1 = Zone 2 ambient thermostat 0 = Absent 1 = Present	0 the	
2.	2.	4	Underfloor thermostat or zone 2 ambient thermostat selection Termoregulation <i>Termoregulation can be a</i> <i>AUTO button.</i> Heating ignition delay Boiler version - NOT TO MODIFY ONLY FOR SERVICE - To b	<ul> <li>0 = Floor safety thermostat</li> <li>1 = Zone 2 ambient thermostat</li> <li>0 = Absent</li> <li>1 = Present</li> <li>0 = Deactivated</li> <li>1 = 10 seconds</li> <li>2 = 90 seconds</li> <li>3 = 210 seconds</li> <li>from 0 to 5</li> <li>0 = Combi</li> </ul>	0 the	
2. 2. 2.	2. 2. 2.	4	Underfloor thermostat or zone 2 ambient thermostat selection Termoregulation <i>Termoregulation can be a</i> <i>AUTO button.</i> Heating ignition delay Boiler version - NOT TO MODIFY ONLY FOR SERVICE - To t substitution P.C.B.	<ul> <li>0 = Floor safety thermostat</li> <li>1 = Zone 2 ambient thermostat</li> <li>0 = Absent</li> <li>1 = Present</li> <li>0 = Deactivated</li> <li>1 = 10 seconds</li> <li>2 = 90 seconds</li> <li>3 = 210 seconds</li> <li>from 0 to 5</li> <li>0 = Combi</li> </ul>	0 the	
2.	2.	4	Underfloor thermostat or zone 2 ambient thermostat selection Termoregulation can be a AUTO button. Heating ignition delay Boiler version - NOT TO MODIFY ONLY FOR SERVICE - To to substitution P.C.B. Boiler nominal power (kW) ONLY FOR SERVICE - To to	0 = Floor safety thermostat 1 = Zone 2 ambient thermostat 0 = Absent 1 = Present <i>activated by pressing</i> 0 = Deactivated 1 = 10 seconds 2 = 90 seconds 3 = 210 seconds from 0 to 5 0 = Combi pe used only in	0 the	
<ol> <li>2.</li> <li>2.</li> <li>2.</li> <li>2.</li> </ol>	2. 2. 2. 2.	4 5 8 9	Underfloor thermostat or zone 2 ambient thermostat selection Termoregulation can be a AUTO button. Heating ignition delay Boiler version - NOT TO MODIFY ONLY FOR SERVICE - To t substitution P.C.B. Boiler nominal power (kW) ONLY FOR SERVICE - To t substitution P.C.B.	0 = Floor safety thermostat 1 = Zone 2 ambient thermostat 0 = Absent 1 = Present <i>activated by pressing</i> 0 = Deactivated 1 = 10 seconds 2 = 90 seconds 3 = 210 seconds from 0 to 5 0 = Combi pe used only in	0 the	
<ol> <li>2.</li> <li>2.</li> <li>2.</li> <li>2.</li> <li>2.</li> </ol>	2. 2. 2. 2. 3	4 5 8 9	Underfloor thermostat or zone 2 ambient thermostat selection Termoregulation <i>Termoregulation can be a</i> <i>AUTO button.</i> Heating ignition delay Boiler version - NOT TO MODIFY ONLY FOR SERVICE - To t substitution P.C.B. Boiler nominal power (kW) ONLY FOR SERVICE - To t substitution P.C.B.	0 = Floor safety thermostat 1 = Zone 2 ambient thermostat 0 = Absent 1 = Present <i>activated by pressing</i> 0 = Deactivated 1 = 10 seconds 2 = 90 seconds 3 = 210 seconds from 0 to 5 0 = Combi pe used only in	0 the	
<ol> <li>2.</li> <li>2.</li> <li>2.</li> <li>2.</li> </ol>	2. 2. 2. 2.	4 5 8 9	Underfloor thermostat or zone 2 ambient thermostat selection Termoregulation can be a AUTO button. Heating ignition delay Boiler version - NOT TO MODIFY ONLY FOR SERVICE - To t substitution P.C.B. Boiler nominal power (kW) ONLY FOR SERVICE - To t substitution P.C.B.	0 = Floor safety thermostat 1 = Zone 2 ambient thermostat 0 = Absent 1 = Present <i>activated by pressing</i> 0 = Deactivated 1 = 10 seconds 2 = 90 seconds 3 = 210 seconds from 0 to 5 0 = Combi pe used only in	0 0 the 0	

5	sub-menu	parameter			s <del>t</del>					
menu	-dn	oara	description	value	default setings					
	0		description	Value	0 0					
2.	3.	2	D.H.W. Maximum power percentage	from 0 to 100 (%)						
			RESERVED FOR TECHNICAL gas or PCB is changed - see							
2.	3.	3	Minimum power percentage	from 0 to 100 (%)						
			RESERVED FOR TECHNICAL gas or PCB is changed - see							
2.	3.	4	C. Heating Maximum power percentage	from 0 to 100 (%)						
			RESERVED FOR TECHNICAL gas or PCB is changed - see							
2.	3.	5	CH Anti-cycling time mode	0 = Manual 1 = Automatic	1					
2.	3.	6	Anti-cycling time (If 235 = 0)	from 0 to 7 (minutes)	3					
2.	3.	7	CI H pump overrun	from 0 to 15 (minutes) or 16 = continuos	3					
2.	3.	8	Pump speed control - NO	TACTIVE						
2.	3.	9	Delta T Pump Set - NOT A	CTIVE						
2.	4	С	ENTRAL HEATING PARAM	ETER - 2						
2.	4.	0	< Not Available>							
2.	4.	1	Warning Pressure	from 4 to 8 (0,x bar)	6					
								if the pressure falls down the boiler will signal a m for insufficient circulatic establishing the correct display.	alfunction warning ( on; the request for	1 <b>P 4</b> ) re-
								/:\	<b>Varning 1P4</b> illing Needed	
2.	4.	2	< Not Available>							
2.	4.	3	Post-ventilation CH	0 = OFF 1 = ON	0					


#### WARNING!!

THE AUTOMATIC CALIBRATION MUST BE DONE IN CASE OF:

- REPLACEMENT OF: FAN, GAS VALVE, AIR/GAS MIXER, BURNER, ELECTRODE.
- REPLACEMENT OF P.C.B.
- GAS CHANGEOVER
- ANY MODIFICATION TO THE FOLLOWING PARAMETERS 220 - SOFT IGNITION
  - 231 MAX CH ADJUSTABLE
  - 232 MAX DHW PERCENTAGE
  - 233 MIN PERCENTAGE
  - 234 MAX CH PERCENTAGE

menu	sub-menu	parameter			default setinas
Ē	ns	pa	description	value	det
2.	4.	4	Boost Time	from 0 to 60 (minutes)	16
			only enabled with Room T temperature adjustment a 421 or 521 or 621 on 01 = B adjustment)	ctivated (parameter Basic temperature	
			This parameter can be use before the automatic incre- in steps of 4°C (max. 12°C) parameter remains at 00 t activated.	ease in flow temperat . If the value of this	
2.	4.	5	Max PWM Pump	from 75 to 100	100
2.	4.	6	Min PWM Pump	from 40 to 100	75
2.	4.	7	CHPressure detection device	0 = Temperature Probes only 1 = Pressure switch 2 = Pressure sensor	2
			ONLY FOR SERVICE - To ta substitution P.C.B.	be used only in	
2.	4.	8	< Not Available>		
<u>2</u> .	4.	9	External temperature	from -3 to +3	0
			correction		
_	-		Only active with external s	sensor connected	
2. 2.	5 5.	0	COMFORT Function	0 = Disabled	0
∠.	Э.	U		1 = Time Based (30 minutes) 2 = Always active	0
			to increase the comfort level hot water. This function keeps the seco periods of boiler inactivity; t status of the water drawn, a higher temperature. When the function is enabled on the display. <b>Note:</b> this function can be ac	ondary exchanger hot d his increases the initial s the water is delivered I the text <b>COMFORT</b> app tivated or deactivated b	uring hea I at a
2.	5.	1	user as well - consult the Use Comfort Anti-cycling Time	from 0 to 120 minutes	0
-	5. 5.	1	Comfort Anti-cycling	from 0 to 120 minutes from 5 to 200	0
-			Comfort Anti-cycling Time	from 0 to 120 minutes	
2.			Comfort Anti-cycling Time DHW start Delay	from 0 to 120 minutes from 5 to 200	
2. 2. 2.	5.	2	Comfort Anti-cycling Time DHW start Delay Anti "water hammering" D.H.W. switch Off logic DHW Post Cooling Post-circulation and post-ventilation after domestic hot water is drawn	from 0 to 120 minutes from 5 to 200 (0.5 to 20 seconds) 0 = Anti-scale (stop at > 67°C) 1 = At 4°C over set-point 0 = OFF 1 = ON	0
2.	5.	2	Comfort Anti-cycling Time DHW start Delay Anti "water hammering" D.H.W. switch Off logic DHW Post Cooling Post-circulation and post-ventilation after domestic hot water is drawn	from 0 to 120 minutes from 5 to 200 (0.5 to 20 seconds) 0 = Anti-scale (stop at > 67°C) 1 = At 4°C over set-point 0 = OFF 1 = ON st-circulation and p hot water draw-off in med requires it.	5 0 0 0 0 0 0 0 0 0 0 0

menu	sub-menu	parameter			default cetinge
Ĕ	ns	ba	description	value	def
2.	6	BC	DILER MANUAL SETTINGS		
2.	6.	0	Manual mode activation	0 = OFF 1 = ON	0
2.	6.	1	Boiler pump control	0 = OFF 1 = ON	0
2.	6.	2	Fan control	0 = OFF 1 = ON	0
2.	6.	3	Diverter valve control	0 = DHW 1 = CH	0
2.	7	TE	ST & UTILITIES	ST & UTILITIES	
2.	7.	0	Test mode	0 = OFF 1 = ON	0
			Press the programming ke The boiler is forced to the power. Turning the encoder allow maximum or minimum pow It is possible to activate th (Chimney active) by pressi 10 seconds.	maximum heating rs for selecting the D. wer operating mode e Cleaning Function ing the Reset button	
2.	7.	1	Air-purge Function	0 = OFF 1 = ON	
		Press the programming key $\mathbf{b}$ and press OK. The Deaeration Cycle can be activated by press the MODE button for 5 seconds.			
2.	7.	2	Automatic Calibration	0 = OFF 1 = ON	
			ESERVED FOR TECHNICAL A paragraph Combustion check		
2.	8	RE	SET MENU' 2		
2.	8.	0	Reset Factory Settings	Reset OK = yes ESC = no	
			To reset all default parame button	eter settings, press the	e OK
4	zc	NE	1 PARAMETERS		
4.	0	SE	TPOINT		
4.	0.	2	T set Zone 1	from 35 to 82 (°C) (high temperature)	70
				from 20 to 45 (°C) (low temperature)	25
	6		To set only with Fixed Flow	v lemperaure (see 4	21)
4.	2		ONE 1 SETTINGS	0 frag 00 i	4
4.	2.	0	Zone 1 Temperature range	0 = from 20 to 45°C (low temperature) 1 = from 35 to 82°C (high temperature)	1
4.	2.	1	Thermoregulation To enabled thermoregulation press Auto button. On the dispaly will appear the symbol AUTO	0 = Fixed Flow Temperature 1 = Basic Thermoregulation 2 = Room Temp only 3 = Outdoor Temp. only 4 = Room + outdoor Temp.	1



menu	sub-menu	description	value	default setings				
5	5 ZONE 2 PARAMETERS							
5.	0	SETPOINT						
<b>F</b>	~	<b>1</b> Test Zame 2		70				

5	20	ZONE Z PARAMETERS						
5.	0	SETPOINT						
5.	0.	2	T set Zone 2	from 35 to 82 (°C) (high temperature) from 20 to 45 (°C)	70 25			
			To and a should be first of files	(low temperature)				
			To set only with Fixed Flor Thermoregulation (see 5					
5.	2	ZC	ONE 2 SETTING					
5.	2.	0	Zone 2 Temperature range	0 = from 20 to 45°C (low temperature) 1 = from 35 to 82°C (high temperature)	1			
5.	2.	1	Thermoregulation To enabled thermoregulation press Auto button. On the dispaly will appear the symbol AUTO	0 = Fixed Flow Temperature 1 = Basic Thermoregulation 2 = Room Temp only 3 = Outdoor Temp. only 4 = Room + outdoor Temp.	1			
5.	2.	2	Slope	from 1.0 to 3.5 (high temperature) from 0.2 to 0.8	1.5 0.6			
			When an outdoor sensor is used, the boiler calculates the most suitable delivery temperature, taking into account the outside temperature and type of system. The type of curve should be selected in correspondence with the projected temperature of the system and the nature of the dispersions present in the structure. For high- temperature systems, one of the curves depicted					
5.	2.	3	below may be chosen. Offset Auto Function active	from - 14 to + 14 (°C) (high temperature)	0			
				from - 7 to + 7 (°C) (low temperature)	0			
			(low temperature)To adapt the heating curve to the system requirements, shift the curve in parallel so that the calculated flow temperature is modified, in addition to the room temperature.By accessing the parameter and pressing the button <b>b</b> , it is possible to shift the curve in a parallel direction. The shifting value can be read on the display: from -14 to +14 for high-temperature devices, or from -7 to 7 for low-temperature devices.Each step corresponds to a 1°C increase/decrease In the flow temperature with respect to the set-point value.					
5.	2.	4	Room Influence Proportional Auto Function active	from 0 to 20	20			
			If setted = 0 the room terr influence the calculation of If setted = 20, the room terr maximun influence to calc - only active when the BU	of the set-point. Emperature has the culate the set-point	d			

menu	sub-menu	parameter	description	value	default setings	
5.	2.	5	Maximum CH Temperature Zone 2	from 35 to 82 °C (Param. 520 = 1)	82	
				from 20 to 45 °C (Param. 520 = 0)	45	
5.	2.	<b>2.6</b> Minimum CH Temperature Zone 2from 35 to 82 °C (Param. 520 = 1)			35	
				from 20 to 45 °C (Param. 520 = 0)		
5.	3	Z2	DIAGNOSTICS		-	
5.	3.	4	Heat request Zone 2	0 = OFF 1 = ON		
6	ZC	NE	3 PARAMETER			
6.	0	SE	TPOINT			
6.	0.	2	T set Zone 3 To set only with Fixed Flo	from 35 to 82 (°C)	70	
			Thermoregulation (see 5			
6.	2	zo	ONE 3 SETTING	521)		
6.	2.	0	Zone 3 Temperature range	0 = from 20 to 45°C (low temperature) 1 = from 35 to 82°C (high temperature)	1	
6.	2.	1	Thermoregulation To enabled thermoregulation press Auto button. On the dispaly will appear the symbol AUTO	0 = Fixed Flow Temperature 1 = Basic Thermoregulation 2 = Room Temp only 3 = Outdoor Temp. only 4 = Room + outdoor Temp.	1	
6.	2.	2	Slope	from 1.0 to 3.5 (high temperature)	1.5	
				from 0.2 to 0.8 (low temperature)	0.6	
			Itdoor sensor is instal is used, the boiler ole delivery temperatu utside temperature ar of curve should be use with the projected in and the nature of the estructure. For high- e of the curves depict	ure, nd I		

	2	ter				
menu	sub-menu	parameter			nult	
ů	sub	pai	description	value	default setings	
6.	2.	3	Offset	from - 14 to + 14 (°C)	0	
			Auto Function active	(high temperature)	0	
				from - 7 to + 7 (°C) (low temperature)	0	
				t the heating curve to the system require-		
	ments, shift the curve in parallel so that the ted flow temperature is modified, in addition					
	room temperature.				uic	
			By accessing the param button <b>b</b> , it is possible			
			parallel direction. The sh			
			on the display: from -14 to devices, or from -7 to 7 for			
			Each step corresponds to	a 1°C increase/decre	ease	
			In the flow temperature wi value.	th respect to the set-p	point	
6.	2.	4	Room Influence	from 0 to 20	20	
-	-		Proportional		-	
			Auto Function active			
			If setted = 0 the room tem influence the calculation of			
			If setted = 20, the room te			
			maximun influence to calc - only active when the BUS		ł	
6.	2.	5	Maximum CH	from 35 to 82 °C	82	
			Temperature Zone 3	(Param. 620 = 1)		
				from 20 to 45 °C (Param. 620 = 0)	45	
6.	2.	6	Minimum CH	from 35 to 82 °C	35	
			Temperature Zone 3	(Param. 620 = 1)		
				from 20 to 45 °C (Param. 620 = 0)	20	
6.	3	Z3	DIAGNOSTICS			
6.	3.	0	< Not Available>			
6.	3.	Δ	11	equest Zone 2 0 = OFF		
8		-	Heat request Zone 2	1 = ON		
	SF			1 = ON		
		RV	ICE PARAMETERS	1 = ON		
8. 8.	SE 0 0.	RV	ICE PARAMETERS DILER STATISTICS - 1			
8.	0	RV BC	ICE PARAMETERS	nx10)		
8. 8.	0 0.	RV BC 0	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. (	inx10) ))		
8. 8. 8.	0 0. 0.	RV BC 0 1	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. ( Time of circulator on (nx10	inx10) ))		
8. 8. 8. 8.	0 0. 0.	RV BC 0 1 2	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. ( Time of circulator on (nx10 Boiler circulator cycles No	inx10) ))		
8. 8. 8. 8. 8.	0 0. 0. 0.	RV BC 0 1 2 3	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. ( Time of circulator on (nx10 Boiler circulator cycles No Boiler Life Time (hx10)	inx10) ))		
8. 8. 8. 8. 8. 8. 8.	0 0. 0. 0. 0.	RV BC 0 1 2 3 4	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. ( Time of circulator on (nx10 Boiler circulator cycles No Boiler Life Time (hx10) Time of fan ON (hx10)	nx10) )) ). (nx10)		
8. 8. 8. 8. 8. 8. 8. 8.	0 0. 0. 0. 0. 0.	RV B( 0 1 2 3 4 5	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. ( Time of circulator on (nx10 Boiler circulator cycles No Boiler Life Time (hx10) Time of fan ON (hx10) Fan cycles No. (nx10)	inx10) )) ). (nx10)		
8. 8. 8. 8. 8. 8. 8. 8. 8.	0 0. 0. 0. 0. 0. 0.	RV B( 0 1 2 3 4 5 6 7	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. ( Time of circulator on (nx10 Boiler circulator cycles No Boiler Life Time (hx10) Time of fan ON (hx10) Fan cycles No. (nx10) CH flame detection (nx10)	inx10) )) ). (nx10)		
8. 8. 8. 8. 8. 8. 8. 8. 8. 8.	0 0. 0. 0. 0. 0. 0. 0.	RV B( 0 1 2 3 4 5 6 7	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. ( Time of circulator on (nx10 Boiler circulator cycles No Boiler Life Time (hx10) Time of fan ON (hx10) Fan cycles No. (nx10) CH flame detection (nx10) DHW flame detection (nx1	inx10) )) ). (nx10) 0)		
8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8.	0 0. 0. 0. 0. 0. 0. 0. 1	RV BC 0 1 2 3 4 5 6 7 8C	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. ( Time of circulator on (nx10 Boiler circulator cycles No Boiler Life Time (hx10) Time of fan ON (hx10) Fan cycles No. (nx10) CH flame detection (nx10) DHW flame detection (nx1 DILER STATISTICS - 2	(nx10) )) (nx10) 0)		
8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8	0 0. 0. 0. 0. 0. 0. 1 1. 1.	RV BC 0 1 2 3 4 5 6 7 8 0	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. ( Time of circulator on (nx10 Boiler circulator cycles No Boiler Life Time (hx10) Time of fan ON (hx10) Fan cycles No. (nx10) CH flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) Mumber on CH (hx10) Number of Flame Faults (n	nx10) )) . (nx10) 0) 0) (10) (10) (10)		
8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8	0 0. 0. 0. 0. 0. 0. 1. 1. 1. 1.	RV BC 0 1 2 3 4 5 6 7 8 6 7 8 0 1 2 3	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. ( Time of circulator on (nx10) Boiler circulator cycles No Boiler Life Time (hx10) Time of fan ON (hx10) Fan cycles No. (nx10) CH flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) Number of Flame Faults (r Number of ignition Cycle	nx10) )) . (nx10) 0) 0) (10) (10) (10)		
8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8	0 0. 0. 0. 0. 0. 0. 1 1. 1. 1. 1.	RV BC 0 1 2 3 4 5 6 7 8 0 1 2 3 4	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. ( Time of circulator on (nx10) Boiler circulator cycles No Boiler Life Time (hx10) Time of fan ON (hx10) Fan cycles No. (nx10) CH flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) Number of Flame Faults (n Number of Flame Faults (n Number of ignition Cycle Heat request Duration	nx10) )) . (nx10) 0) 0) (10) (10) (10)		
8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8	0 0. 0. 0. 0. 0. 0. 1. 1. 1. 1. 1. 2	RV B( 0 1 2 3 4 5 6 7 8 6 7 8 0 1 2 3 4 80	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. ( Time of circulator on (nx10) Boiler circulator cycles No Boiler Life Time (hx10) Time of fan ON (hx10) Fan cycles No. (nx10) CH flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) Number of Flame Faults (r Number of Flame Faults (r Number of ignition Cycle Heat request Duration	(nx10) )) (nx10) 0) 0) (10) (10) (10) (10) (10) (11) (10) (11) (1)) (1		
8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8	0 0. 0. 0. 0. 0. 0. 1 1. 1. 1. 1.	RV BC 0 1 2 3 4 5 6 7 8 0 1 2 3 4	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. ( Time of circulator on (nx10) Boiler circulator cycles No Boiler Life Time (hx10) Time of fan ON (hx10) Fan cycles No. (nx10) CH flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) Number of Flame Faults (n Number of Flame Faults (n Number of ignition Cycle Heat request Duration	(nx10) )) (nx10) 0) 0) (10) 1x10) rs (nx10) 0 = OFF		
8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 8	0 0. 0. 0. 0. 0. 0. 1. 1. 1. 1. 1. 2	RV B( 0 1 2 3 4 5 6 7 8 6 7 8 0 1 2 3 4 80	ICE PARAMETERS DILER STATISTICS - 1 Diverter valve cycles No. ( Time of circulator on (nx10) Boiler circulator cycles No Boiler Life Time (hx10) Time of fan ON (hx10) Fan cycles No. (nx10) CH flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) DHW flame detection (nx10) Number of Flame Faults (r Number of Flame Faults (r Number of ignition Cycle Heat request Duration	(nx10) )) (nx10) 0) 0) (10) (10) (10) (10) (10) (11) (10) (11) (1)) (1		

menu	sub-menu	parameter		han sei		
me	sub	par	description	default settings		
8.	2.	4	Diverter valve position	0 = D.H.W. 1 = Central Heating		
8.	2.	5	D.H.W. Flow Rate (I/min)			
8.	2.	7	Pump Modulation %			
8.	2.	8	Gas Power (kW)			
8.	3	в	ILER TEMPERTURE			
8.	3.	0	CH Flow set Temperature	(°C)		
8.	3.	1	CH Flow Temperature(°C)			
8.	З.	2	CH Return Temperature(°C	C)		
8.	3.	3	DHW Temperature (°C)			
8.	З.	4	< Not Available>			
8.	З.	5	Outdoor temperature (°C)			
			Only with external sensor	connected		
8.	4	ST	ORAGE			
8.	4.	2	D.H.W. Inlet Temperature (	(°C)		
			Display only with Solar Kit or			
8.	5	SE	RVICE	5		
8.	5.	0	Months to next	from 0 to 60 24		
			maintenance	(month)		
			If setted the boiler will dis	play that is time to call		
			the installer for maintenar	ice		
				Semnalare 3P9		
				tinere programata		
				ati asistenta tehnica		
-	_	-				
8.	5.	1	Maintenance on Day At	0 = OFF		
				1=ON		
8. 8.	5. 5.	1 2	Maintenance on Day At Maintenance Warning Reset			
			Maintenance Warning	1=ON Reset? OK= Yes Esc = No		
			Maintenance Warning Reset	1=ON Reset? OK= Yes Esc = No		
8.	5.	2	Maintenance Warning Reset to erase the advice for ma	1=ON Reset? OK= Yes Esc = No		
8. 8.	5. 5.	2 4 5	Maintenance Warning Reset to erase the advice for ma SW version Interface	1=ON Reset? OK= Yes Esc = No		
8. 8. 8.	5. 5. 5.	2 4 5	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main	1=ON Reset? OK= Yes Esc = No		
8. 8. 8. 8.	5. 5. 5. 6	2 4 5 EF	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors	1=ON Reset? OK= Yes Esc = No aintenance from Fault 0 to Fault 9		
8. 8. 8. 8.	5. 5. 5. 6	2 4 5 EF	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild	1=ON Reset? OK= Yes Esc = No aintenance from Fault 0 to Fault 9 possible to see the last 10		
8. 8. 8. 8.	5. 5. 5. 6	2 4 5 EF	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year.	1=ON Reset? OK= Yes Esc = No aintenance from Fault 0 to Fault 9 possible to see the last 10 er as well as the relevant		
8. 8. 8. 8.	5. 5. 5. 6	2 4 5 EF	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow	1=ON Reset? OK= Yes Esc = No aintenance from Fault 0 to Fault 9 possible to see the last 10 er as well as the relevant <i>y</i> s for viewing the		
8. 8. 8. 8.	5. 5. 5. 6	2 4 5 EF	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow sequence of errors that or	1=ON Reset? OK= Yes Esc = No aintenance from Fault 0 to Fault 9 possible to see the last 10 er as well as the relevant <i>y</i> s for viewing the		
8. 8. 8. 8.	5. 5. 5. 6	2 4 5 EF	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow sequence of errors that our 8.6.0 Last 10 errors	1=ON         Reset? OK= Yes         Esc = No         aintenance         from Fault 0 to Fault 9         possible to see the last 10         er as well as the relevant         vs for viewing the         ccurred, from 0 to 9.		
8. 8. 8. 8.	5. 5. 5. 6	2 4 5 EF	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow sequence of errors that our 8.6.0 Last 10 errors Rest No flame d	1=ON         Reset? OK= Yes         Esc = No         aintenance         from Fault 0 to Fault 9         possible to see the last 10         er as well as the relevant         vs for viewing the         ccurred, from 0 to 9.         3         etected		
8. 8. 8. 8.	5. 5. 5. 6	2 4 5 EF	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow sequence of errors that our 8.6.0 Last 10 errors Fault No flame d 501	1=ON         Reset? OK= Yes         Esc = No         aintenance         from Fault 0 to Fault 9         possible to see the last 10         er as well as the relevant         vs for viewing the         ccurred, from 0 to 9.		
8. 8. 8. 8.	5. 5. 5. 6	2 4 5 EF	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow sequence of errors that our 8.6.0 Last 10 errors Rest No flame d	1=ON         Reset? OK= Yes         Esc = No         aintenance         from Fault 0 to Fault 9         possible to see the last 10         er as well as the relevant         vs for viewing the         ccurred, from 0 to 9.		
8. 8. 8. 8.	5. 5. 5. 6	2 4 5 EF	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow sequence of errors that our 8.6.0 Last 10 errors Fault No flame d 501	1=ON         Reset? OK= Yes         Esc = No         aintenance         from Fault 0 to Fault 9         possible to see the last 10         er as well as the relevant         vs for viewing the         ccurred, from 0 to 9.         3         etected         p1/2012         Reset?		
8. 8. 8. 8.	5. 5. 6 6.	2 4 5 EF	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow sequence of errors that ou 8.6.0 Last 10 errors Raut No flame d 501 12:18 24/0	1=ON         Reset? OK= Yes         Esc = No         aintenance         from Fault 0 to Fault 9         possible to see the last 10         eras well as the relevant         vs for viewing the         ccurred, from 0 to 9.         3         etected         p1/2012         Reset?         Ok=Yes		
8. 8. 8. 8. 8.	5. 5. 6 6.	2 4 5 EF 0	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow sequence of errors that ou 8.6.0 Last 10 errors Fault No flame d 501 12:18 24/ Reset Error List	1=ON         Reset? OK= Yes         Esc = No         aintenance         from Fault 0 to Fault 9         possible to see the last 10         er as well as the relevant         vs for viewing the         ccurred, from 0 to 9.         3         etected         p1/2012         Reset?		
8. 8. 8. 8. 8. 8. 8.	5. 5. 6 6. 6. 7	2 4 5 EF 0	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow sequence of errors that out 8.6.0 Last 10 errors Fault No flame d 50 f 12:18 24/0 Reset Error List	1=ON         Reset? OK= Yes         Esc = No         aintenance         from Fault 0 to Fault 9         possible to see the last 10         er as well as the relevant         vs for viewing the         ccurred, from 0 to 9.         3         etected         01/2012         Reset?         0k=Yes         Esc=No		
8. 8. 8. 8. 8.	5. 5. 6 6.	2 4 5 EF 0	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow sequence of errors that ou 8.6.0 Last 10 errors Fault No flame d 501 12:18 24/ Reset Error List	1=ON         Reset? OK= Yes         Esc = No         aintenance         from Fault 0 to Fault 9         possible to see the last 10         eras well as the relevant         vs for viewing the         ccurred, from 0 to 9.         3         etected         p1/2012         Reset?         Ok=Yes		
8. 8. 8. 8. 8. 8. 8.	5. 5. 6 6. 6. 7	2 4 5 EF 0	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow sequence of errors that out 8.6.0 Last 10 errors Fault No flame d 50 f 12:18 24/0 Reset Error List	1=ON         Reset? OK= Yes         Esc = No         aintenance         from Fault 0 to Fault 9         possible to see the last 10         er as well as the relevant         vs for viewing the         ccurred, from 0 to 9.         3         etected         0//2012         Reset?         Ok=Yes         Esc=No         0 = Open		
8. 8. 8. 8. 8. 8. 8. 8.	5. 5. 6 6. 6. 7 7. 7.	2 4 5 EF 0 1 1 FF 4 6	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow sequence of errors that or 8.6.0 Last 10 errors Fault No flame d 501 12:18 24// Reset Error List EEE PARAMETERS Boiler Flowswitch	1=ON         Reset? OK= Yes         Esc = No         aintenance         from Fault 0 to Fault 9         possible to see the last 10         er as well as the relevant         vs for viewing the         ccurred, from 0 to 9.         3         etected         p1/2012         Reset?         Ok=Yes         Esc=No         0 = Open         1 = Closed		
8. 8. 8. 8. 8. 8. 8. 8. 8.	5. 5. 6 6. 6. 7 7. 7.	2 4 5 EF 0 1 1 FF 4 6 - F	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow sequence of errors that or 8.6.0 Last 10 errors Fault No flame d 501 12:18 24// Reset Error List Boiler Flowswitch Safety flame sensor	1=ON         Reset? OK= Yes         Esc = No         aintenance         from Fault 0 to Fault 9         possible to see the last 10         er as well as the relevant         vs for viewing the         ccurred, from 0 to 9.         3         etected         p1/2012         Reset?         Ok=Yes         Esc=No         0 = Open         1 = Closed		
8. 8. 8. 8. 8. 8. 8. 8. 8. 8. 19	5. 5. 6 6. 7 7. 7. WI	2 4 5 EF 0 1 1 FF 4 6 - F	Maintenance Warning Reset to erase the advice for ma SW version Interface SW version Main ROR HISTORY Last 10 Errors This parameter makes it p errors shown by the boild day, month and year. Turning the encoder allow sequence of errors that or 8.6.0 Last 10 errors Fault No flame d 501 12:18 24/ Reset Error List Reset Error List Boiler Flowswitch Safety flame sensor I (only for ALTEAS ONE)	1=ON         Reset? OK= Yes         Esc = No         aintenance         from Fault 0 to Fault 9         possible to see the last 10         er as well as the relevant         vs for viewing the         ccurred, from 0 to 9.         3         etected         p1/2012         Reset?         Ok=Yes         Esc=No         0 = Open         1 = Closed		

	-		I	1			
menu	sub-menu	parameter	description	value	default setings		
19.	0.	1	Network configuration	0 = OFF 1 = ON			
19.	0.	2	<not available=""></not>				
19.	0.	3	Internet time	0 = OFF 1 = ON			
19.	1	Co	onnectivity Info				
19.	1.	0	Connectivity status				
19.	1.	1	Signal level				
19.	1.	2	Active Status	Active Status			
19.	1.	4	Serial Number				
19.	1.	5	SW Upgrade Status				
19.	2	Re	set Menu				
19.	2.	0	Factory Reset (soft reset)	Do you really want to perform the reset? if you press OK button, the reset command will be executed otherwise, by way of ESC, the previous page is shown.			

#### Important

Maintenance is an essential part of the safe and efficient operation of the boiler and ensures its durability. It should be performed according to the instructions given in current legislation. Perform combustion analysis regularly in order to check the operating efficiency of the boiler and to make sure any polluting substances released are within the boundaries set by current legislation.

Before beginning maintenance work:

- Disconnect the appliance from the electricity supply by turning the external bipolar switch to the "OFF" position;
- Close the gas valve and the central heating and domestic hot water system valves.

After the work has been completed the initial settings will be restored.

#### **General comments**

It is recommended that the following inspections be carried out on the boiler at least once a year:

- 1. Check the seals in the water part and, if necessary, replace the gaskets and restore the seal to perfect working order.
- 2. Check the seals in the gas part and, if necessary, replace the gaskets and restore the seal to perfect working order.
- Visually check the overall condition of the boiler.
   Visually check and, if necessary, disassemble and clean
- the burner.
- 5. Following the inspection detailed in point "3", disassemble and clean the combustion chamber, if necessary.
- 6. Following the inspection detailed in point "4", disassemble and clean the burner, if necessary.
- 7. Cleaning the primary heat exchanger
- 8. Make sure the following heating safety devices are operating correctly:
- temperature limit safety device.
- 9. Make sure that the following gas part safety devices are operating correctly:
- absence of gas or flame safety device (ionisation).
- 10. Check the efficiency of the domestic hot water production process (test the flow rate and temperature).
- 11. Perform a general inspection of the boiler operation.
- 12. Remove oxide from the detection electrode using an emery cloth.
- These checks are not exhaustive. Further mechanical, electrical and combustion maintenance checks may be required.

#### WARNING!!

# THE AUTOMATIC CALIBRATION MUST BE DONE IN CASE OF:

- REPLACEMENT OF: FAN, GAS VALVE, AIR/GAS MIXER, BURNER, ELECTRODE.
- REPLACEMENT OF P.C.B.
- GAS CHANGEOVER
- ANY MODIFICATION TO THE FOLLOWING PARAMETERS
  - 220 SOFT IGNITION
  - 231 MAX CH ADJUSTABLE
  - 232 MAX DHW PERCENTAGE
  - 233 MIN PERCENTAGE
  - 234 MAX CH PERCENTAGE

#### **Operational test**

After having carried out the maintenance operations, fill the heating circuit at a pressure of approximately 1.5 bar and release the air from the system.

Fill the domestic hot water system at the same time.

- Begin operating the boiler.
- If necessary, release the air from the heating system again.
- Check the settings and make sure all the command, adjustment and monitoring parts are working correctly.
- Check the flue system is sealed and operating correctly.

#### Draining procedures

- The heating system must be drained using the following procedure:
- Switch off the boiler, make sure the external bipolar switch is in the OFF position and shut off the gas valve;
- Loosen the automatic air relief valve;
- Open the system drain off cock and collect the escaping water in a container;
- Empty the water from the lowest points of the system (where applicable).

If the system is to be left inactive in areas where the room temperature may fall below 0°C during winter, we recommend that anti-freeze liquid is added to the water in the heating system in order to avoid the need for repeated draining; when this liquid is used make sure it is compatible with the stainless steel used for the bodywork of the boiler.

We recommend the use of anti-freeze products which contain PROPYLENE GLYCOLS as these inhibit corrosion and that they are used in conjunction with the anti-scaling and anti-corrosion function, in the quantities suggested by the manufacturer, at the mimimum temperature.

Regularly check the pH level of the water/anti-freeze mix in the boiler circuit and replace it when the value measured is lower than the limit prescribed by the manufacturer.

#### DO NOT MIX DIFFERENT TYPES OF ANTI-FREEZE.

The manufacturer will not be held liable for any damage caused by the appliance or the system due to the use of inappropriate anti-freeze substances or additives.

#### Draining the domestic hot water system and indirect cylinder

Every time there is a danger of freezing, the domestic hot water system must be drained as follows:

- Shut off the water mains inlet valve;
- Open all the hot and cold water taps;
- Empty the water from the lowest points of the system (where applicable).

#### WARNING

Before handling, empty all components which may contain hot water, performing bleeding where necessary.

Descale the components in accordance with the instructions provided on the safety data leaflet supplied with the product used, make sure the room is well ventilated, wear protective clothing, avoid mixing different products, and protect the appliance and surrounding objects.

Seal all openings used to take a gas pressure reading or to make any gas adjustments.

If a smell of burning is detected or smoke is seen leaking from the appliance, or there is a smell of gas, disconnect it from the electricity supply, shut off the gas valve, open the windows and call for technical assistance.

#### Cleaning the primary exchanger

Cleaning the combustion side

The inside of the primary exchanger is accessed by removing the burner. Wash with water and detergent using a non-metallic rifle-type brush, rinse with water.



#### Cleaning the trap

The trap is accessed by emptying the condensate bowl located in the bottom section. Wash with water and detergent. Replace the condensate collection bowl in its housing. NB: In the event of prolonged use of the appliance, the trap must be filled before being used again. A lack of water in the trap is dangerous and may cause products to be released into the atmosphere.

ARISTON 46/

#### **1. GENERAL ACCESS**


#### 1.0 Disconnect the boiler


Before beginning maintenance work:


 a. Disconnect the appliance from the electricity supply. Press the ON/OFF button and wait 1 minute (the 3-way valve turn on Stand-by position)
 ATTENTION!! With the 3-way valve on heating position is not possible to remove the motor.

Turn the external bipolar switch to the "OFF" position.


b. Close the gas valve and the central heating and domestic hot water system valves.










#### 2. ELECTRICAL UNIT













#### **3. HYDRAULIC UNIT**












Remove the clip and lift the diverter valve from the assembly.





WHEN REASSEMBLING, ENSURE THE DIVERTER VALVE IS ALIGNED CORRECTLY.




















Drain primary and domestic hot water circuits. Remove the silencer.



TIME 🔘 10 min


Remove the two screws and remove the heat exchanger







# 3.12 Condensate trap Tools TIME 5 min Disconnect the condensate discherge pipe from the bottom of


Disconnect the condensate discherge pipe from the bottom of the boiler. Unscrerw the two screws.




Disconnect the condensate pipe from the condensate trap











TEMPERATURE	RESISTANCE (kOhm)
0	27
10	17
20	12
25	10
30	8
40	5
50	4







3.16 Main heat exchanger

0


Drain boiler (see 3.3)

Remove the silencer

Tools

**MAINTENANCE GUIDE** 

TIME Ö 20 min




```
      6
```






Disconnect the condensate pipe







#### 4. BURNER UNIT



Legend:

- 1 Ceramic fibre
- 2 Burner
- 3 Silencer
- 4 Mixing tube
- 5 Fan
- 6 Detection/Ignition electrode







4.2 Burner

Remove the four nuts and remove the burner unit

3










Remove the ceramic fibre.

Remove the four screws and pull the burner toward you. **Always replace the burner gasket** (\*).




Verify and replace the other gaskets if they are damaged or showing signs of deterioration






1




Fan & mixer venturi according to the model					
Power Fan Venturi diameter					
30 kW	EBM 118 85W	Ø 18,7			
38 kW	EBM 118 85W	Ø 21,6			

# 4.4 Gas Valve

Remove the two screws under the boiler and disconnect the gas pipe on the top of the gas valve



Remove the gas valve





Legend: 1 - Inlet test point

#### **5. ANNUAL MAINTENANCE**

Plate heat exchanger	
Maintenance Interval: As necessary	Contraction of the second seco
How: To measure specification of DHW performance.	
	1 contraction of the second se
	5
By-pass & Safety valve	
Maintenance Interval: Annually	
How: Visual inspection / Clean as necessary	
The state inspection / clean as necessary	
Central heating filter	
Maintenance Interval: Annually	
How: Visual inspection / Clean as necessary	
Flow switch operation	
Maintenance Interval: Annually	
How: Visual inspection / Clean as necessary / Check flow rate	
Expansion vessel	
Maintenance Interval: Annually	
How: Check air pressure is at 15 psi (System drained)	
riow. eneek un pressure is at its psilogstern arannedy	
	)
Ignition & detection electrode	1
Maintenance Interval: Annually	- The second sec
How: Visual inspection / Clean as necessary / Distance from the burner / Ionisation current	
more than 1 µA	
	27
	•
Burner	
Maintenance Interval: Annually	
How: Visual inspection / Clean as necessary	
Fan	and the second s
Maintenance Interval: Annually	
How : Visual inspection / Clean as necessary	



### **TECHNICAL DATA**

	Model:		ALTEAS	ONE NET
Ļ			30	35
ERA	CE Certification (pin)		00850	R0394
GENERAL	Boiler type		C53(X)-C63(X)	33(X)-C43(X)- C83(X)-C93(X) 3P-B33
	Max/min nominal calorific flow rate (Pci)Qn		28.0 / 3.0	31.0 / 3.5
	Max/min nominal calorific flow rate (Pcs) Qn		31.1 / 3.0	34.4 / 3.9
	Domestic hot water max/min nominal calorific flow rate (Pci) Qn	kW	30.0 / 3.0	34.5 / 3.5
(0	Domestic hot water max/min nominal calorific flow rate (Pcs)	kW	33.3 / 3.3	38.3 / 3.9
ŇÖ	Max/min power output (80°C-60°C) Pn	kW	27.5 / 2.8	30.3 / 3.3
ATI	Max/min power output (50°C-30°C)Pn	kW	30.3 / 3.1	33.5 / 3.6
	Domestic hot water max/min power output Pn	kW	28.7 / 2.9	33.1 / 3.4
БЕС	Combustion efficiency (of flue gas)	%	97.8	97.8
S S S	Nominal calorific flow rate efficiency (60/80°C) Hi/Hs	%	98.4 / 88.6	97.7 / 88.0
POWER SPECIFICATIONS	Nominal calorific flow rate efficiency (30/50°C) Hi/Hs	%	108.3 / 97.5	108.0 / 97.2
E E	Efficiency at 30% at 30°C (condensation) Hi/Hs	%	109.5 / 98.6	109.5 / 98.6
	Minimum calorific flow rate efficiency (60/80°C) Hi/Hs	%	93.0 / 83.8	93.5 / 84.2
	Efficiency rating (dir. 92/42/EEC)	stars	**	**
	Loss of burner gas when operating	%	2.2	2.2
	Available air pressure	Pa	100	100
	NoX class	class	6	
S	Flue gas temperature (G20) (80°C-60°C)	°C	66	66
NOI	CO2 content (G20) (80°C-60°C)	%	8.8	8.8
EMISSIONS	CO content (0%O2) (80°C-60°C)	ppm	102.2	98.8
Ш	O2 content (G20) (80°C-60°C)	%	3.8	4.5
	Maximum flue gas flow (G20) (80°C-60°C)	Kg/h	47.6	55.7
	Excess air (80°C-60°C)	%	22	27
	Expansion chamber inflation pressure	bar	1	
UIT NG	Maximum heating pressure	bar	3	
HEATII CIRCL	Expansion chamber capacity	I	8	
뿌퉁	Min/max heating temperature (high temperature range)	°C	35	/ 82
	Min/max heating temperature (low temperature range)	°C	20	/ 45
ËR	Domestic hot water max/min temperature	°C	36	60
NAT	Specific flow rate of domestic hot water ( $\Delta T=30^{\circ}C$ )		14.3	16.5
10 T	Quantity of hot water $\Delta T=25^{\circ}C$	l/min	17.2	19.8
DOMESTIC HOT WATER CIRCUIT	Quantity of hot water $\Delta T=35^{\circ}C$	l/min	12.3 14.1	
CI	Hot water comfort rating (EN13203)	stars	***	
ME	Hot water minimum flow rate	l/min	2	2
ă	Domestic hot water max/min pressure		7.0 / 0.2	
	Power supply frequency/voltage		230	/ 50
AL	Total electrical power absorbed		91 82	
L RIC	Circulation Pump energy efficiency index		EEI ≤	0,23
ELECTRICAL	Minimum ambient temperature for use	°C	+	5
Ш	Protection level for the electrical appliance	IP	X	5D
	Weight	kg	35,3	37,6

#### ErP Data - EU 813/2013

Model: ALTEAS ONE NET		30	35
Condensing boiler	yes/no	yes	yes
Low-temperature boiler:	yes/no	no	no
B1 boiler	yes/no	no	no
Cogeneration space heater	yes/no	no	no
Combination heater	yes/no	yes	yes
Contact details (Name and address of the manufacturer or its authorised representative)		Viale A. Merl	IERMO S.p.A. oni 45 60044 AN - ITALIA
ErP HEATING			
Power output Pn	kW	28	31
Useful heat output at rated heat output and high-temperature regime $\ \ P_4$	kW	28.0	31.0
Useful heat output at 30 % of rated heat output and low-temperature regime (Return temperature 30°C) P1	kW	8.4	9.3
Seasonal space heating energy efficiency $\eta_S$	%	94	94
Useful efficiency at rated heat output and high-temperature regime (60-80°C) $\eta_4$	%	88.6	88.0
Useful efficiency at 30 % of rated heat output and low-temperature regime (Return temperature 30°C) $\eta_1$	%	98.6	98.6
ErP D.H.W.			
Declared load profile		XL	XXL
Water heating energy efficiency N <sub>Wh</sub>	%	85	86
Daily electricity consumption Q <sub>elec</sub>	kWh	0.220	0.230
Daily fuel consumption Q <sub>fuel</sub>	kWh	22.770	28.460
AUXILIARY ELECTRICITY CONSUMPTION			i .
At full load elmax	kW	0,042	0,042
At part load elmin	kW	0,014	0,014
In standby mode P <sub>SB</sub>	kW	0,005	0,005
OTHER ITEMS			I
Standby heat loss P <sub>Stby</sub>	kW	0.0045	0.046
Ignition burner power consumption P <sub>ign</sub>	kW	0.000	0.000
Sound power level, indoors L <sub>WA</sub>	dB	54	51
Emissions of nitrogen oxides NOx	mg/kWh	33	35

#### **TECHNICAL DATA**

PRODUCT FICHE - EU 811/2013						
Brand	ARISTON					
Model		ALTEAS	ALTEAS ONE NET			
	-	30	35			
Declared load profile		XL	XXL			
Seasonal space heating energy efficiency class		A	A			
Water heating energy efficiency class		A	A			
Power output Pn	kW	28	31			
Annual energy consumption Q <sub>HE</sub>	GJ	48	54			
Annual electricity consumption AEC	kWh	49	50			
Annual fuel consumption AFC	GJ	18	23			
Seasonal space heating energy efficiency $\eta_S$	%	94	94			
Water heating energy efficiency $\eta_{\text{WH}}$	%	85	86			
Sound power level, indoors L <sub>WA</sub>	dB	54	51			


PRODUCT FICHE - CUBE - WiFi Room sensor					
Brand	ARISTON				
Supplier identification model	CUBE WIFI				
Temperature control class	VI				
Energy efficiency contribution for space heating %	4%				

#### Important!!

The installation of the boiler and all the included thermoregulation accessories determines a final value of Seasonal space heating energy efficiency ( $\eta_s$ ) as shown in the table below for the various models.

Brand	ALTEAS ONE NET			
		30	35	
Seasonal space heating energy efficiency $\eta_s$	%	94+4 =98	94+4 =98	
		A <sup>+</sup>	A <sup>+</sup>	

#### Package fiche



#### Instructions for filling the label for packages of space heater (or combination heater), temperature control and solar device.

- 1. supplier's name or trademark;
- 2. supplier's model identifier;
- 3. the seasonal space heating energy efficiency class of the space heater, already filled;
- 4. the seasonal space heating and water heating energy efficiency classes of the combination heater already filled;
- 5. Indication **N** of whether a solar collector, hot water storage tank, temperature control and/or supplementary heater, may be included in the package of combination heater, temperature control and solar device;
- 6. the seasonal space heating energy efficiency class of the package of combination heater, temperature control and solar device, determined in accordance with the figure 1 in the following pages.

The head of the arrow containing the seasonal space heating energy efficiency class of the package of combination heater, temperature control and solar device shall be placed at the same height as the head of the relevant energy efficiency class;

7. the water heating energy efficiency class of the package of combination heater, temperature control and solar device, determined in accordance with the figure 5 in the following pages.

The head of the arrow containing the water heating energy efficiency class of the package of combination heater, temperature control and solar device shall be placed at the same height as the head of the relevant energy efficiency class.

The energy efficiency of the package of products provided for this fiche may not correspond to its actual energy efficiency once installed in a building, as the efficiency is influenced by further factors such as heat loss in the distribution system and the dimensioning of the products in relation to building size and characteristics.



PACKAGES OF COMBINATION HEATER, TEMPERATURE CONTROL AND SOLAR DEVICE

The fiche for packages of combination heater, temperature control and solar device shall contain the elements set out in points (a) and (b):

- a) the elements set out in Figure 1, respectively, for evaluating the seasonal space heating energy efficiency of a package of combination heater, temperature control and solar device, including the following information:
  - I: the value of the seasonal space heating energy efficiency of the preferential combination heater, expressed in %;
  - II: the factor for weighting the heat output of the preferential and supplementary heaters of a package (see COMMISSION DELEGATED REGULATION (EU) No 811/2013 - annex IV - 6.a);
  - III: the value of the mathematical expression: 294/(11 · Prated), whereby Prated is related to the preferential combination heater;
  - IV: the value of the mathematical expression 115/(11 · Prated), whereby Prated is related to the preferential combination heater;
- in addition, for preferential heat pump combination heaters:
  - -V: the value of the difference between the seasonal space heating energy efficiencies under average and colder climate conditions, expressed in %;
  - -VI: the value of the difference between the seasonal space heating energy efficiencies under warmer and average climate conditions, expressed in %;
- (b) the elements set out in Figure 5 for evaluating the water heating energy efficiency of a package of combination heater, temperature control and solar device, where the following information shall be included:
  - I: the value of the water heating energy efficiency of the combination heater, expressed in %;
  - II: the value of the mathematical expression (220 · Q ref )/Q nonsol, where Q ref is taken from Table 15 in Annex VII of the COMMISSION DELEGATED REGULATION (EU) N. 811/2013 and Q nonsol from the product fiche of the solar device for the declared load profile M, L, XL or XXL of the combination heater;
  - III: the value of the mathematical expression (Qaux · 2,5)/ (220 · Qref), expressed in %, where Q aux is taken from the product fiche of the solar device and Q ref from Table 15 in Annex VII of the COMMISSION DELEGATED REGULATION (EU) N. 811/2013 for the declared load profile M, L, XL or XXL.

X

X

Seasonal space heating energy efficiency of boiler	<b>1</b> 1′ %
Temperature control From fiche of temperature control V = 3%, $VI = 4%$ , $VII = 3,5%$ , $VIII = 5%$	+%
Supplementary boiler From fiche of boiler ( Seasonal space heating energy efficiency (in %) ( -'I') x 0,1 =	€ ±%
Solar contribution - From fiche of solar device	
Collector size ( in m²)Tank volume ( in m³)Collector efficiency ( in %)Tank rating $A^* = 0.95, A = 0.91, B = 0.86, C = 0.83, D-G = 0.81$ ( 'III' x + 'IV' x ) x 0.9 x ( /100 ) x =	<b>4</b> +%
Supplementary heat pump From fiche of heat pump ( 'l' ) x 'll' =	<b>5</b> +%
Solar contribution and supplementary heat pump	
Select smaller value         0,5 x         OR         0,5 x         =	%
Seasonal space heating energy efficinency of package	<b>Ø</b> %
Seasonal space heating energy efficinency class of package	
G       F       E       D       C       B       A       A <sup>++</sup> A <sup>+++</sup> $< 30\% \ge 30\% \ge 34\% \ge 36\% \ge 75\% \ge 82\% \ge 90\% \ge 98\% \ge 125\% \ge 150\%$	
Boiler and supplementary heat pump installed with low temperature heat emitters at 35 °C? From fiche of heat pump	

The energy efficiency of the package of products provided for this fiche may not correspond to its actual energy efficiency once installed in a building, as the efficiency is influenced by further factors such as heat loss in the distribution system and the dimensioning of the products in relation to building size and characteristics.

+(50 x'II') =


%

/71 ARISTON

#### **TECHNICAL DATA**

#### Figure 5


Water heating energy efficiency of combination heater



Water heating energy efficiency class of package under average climate

(													
			G	F	E	D	С	В	A	A <sup>+</sup>	A <sup>++</sup>	A <sup>+++</sup>	
	Μ		< 27 %	≥ 27 %	≥ 30 %	≥ 33 %	≥ 36 %	≥ 39 %	≥ 65 %	≥ 100 %	≥ 130 %	≥ 163 %	
	L		< 27 %	≥ 27 %	≥ 30 %	≥ 34 %	≥ 37 %	≥ 50 %	≥ 75 %	≥ 115 %	≥ 150 %	≥ 188 %	
			< 27 %	≥ 27 %	≥ 30 %	≥ 35 %	≥ 38 %	≥ 55 %	≥ 80 %	≥ 125 %	≥ 160 %	≥ 200 %	
	XX	L	< 28 %	≥ 28 %	≥ 32 %	≥ 36 %	≥ 40 %	≥ 60 %	≥ 85 %	≥ 131 %	≥ 170 %	≥ 213 %	

Water heating energy efficiency under colder and warmer climate conditions



The energy efficiency of the package of products provided for this fiche may not correspond to its actual energy efficiency once installed in a building, as the efficiency is influenced by further factors such as heat loss in the distribution system and the dimensioning of the products in relation to building size and characteristics.

#### GAS BOILER SYSTEM COMMISSIONING CHECKLIST

This Commissioning Checklist is to be completed in full by the competent person who commissioned the boiler as a means of demonstrating compliance with the appropriate Building Regulations and then handed to the customer to keep for future reference.

Failure to install and commission according to the manufacturer's instructions and complete this Benchmark Commissioning Checklist will invalidate the warranty. This does not affect the customer's statutory rights.

<form>Calcite rankerContension of mande!Boler and made!Boler and made!Boler and made!Boler and made!Company name:Company name:<th>Customer name:</th><th></th><th></th><th></th><th></th><th>То</th><th>lonhon</th><th>0 0110</th><th>abor:</th><th></th><th></th><th></th><th></th><th></th><th></th><th></th><th></th></form>	Customer name:					То	lonhon	0 0110	abor:									
<form>Balar rande and model:Balar serie and model:Sais Safe register number:Image: Safe register number:Commissioned fuelts TI NAKE;Sais Safe register number:Sais Safe register number:Company adries:Telephone number:Sais Safe register number:Company adries:Commissioned fueltsSais Safe register number:Company adries:Commissioned fueltsCompany adries:Commissioned fueltsCompany adries:Commissioned fueltsCommissioned fueltsSafe Safe register number:Building Regulations Notification Number (flagplicatile):Room thermostal ad programmer/timerTime and temperature control to hearingLoad/weather compensationMaing and valuesCylinder thermostal and programmer/timerNot requiredHadring Zoos valuesFittedVot requiredAutomatic ValuesFittedVot requiredAutomatic Values as discontrol to hearingNot requiredNot requiredAutomatic Values as used?FittedVot requiredAutomatic Values as used?FittedVot requiredAutomatic Values as used?Safe Main Market and Index and Inde</form>						le	lephon	enun	ibei.									
Dates sand number:Case Safe register number:Case Safe register number:Case Safe register number:Commissioned by (PRINT NAME):Case Safe register number:Case Safe register number:Commissioned by CRINT NAME in the safe register number:Commissioned by CRINT NAME in the safe register number:Case Safe register number:Commissioned by the customer on receipt of a building Regulations Compliance Certificate'Commissioned safeThe and temperature control to heatingRoom temmestit and programmer/InterProgrammer interThe and temperature control to heatingCommission and programmer/InterProgrammer interThe and temperature control to heatingCommission and programmer/InterProgrammer interThe and temperature control to heatingCommission and programmer/InterProgrammer interThe safe number is safe register number:FittedNot requiredThe and temperature control to heatingCommission and programmer/InterNot requiredThe and temperature control to heatingCommission and programmer/InterNot requiredThe and temperature control to heatingFittedNot requiredThe safe number is safe register number:FittedNot requiredThe safe number is safe register																		
Commissioned by (PRINT NAME):         Gas Safe register number:         Company addres:           Company addres:         Commissioning date         Commissioning date           Company addres:         Commissioning date         Environitation (adderes):           Company addres:         Commissioning date         Environitation (adderes):           CONTROLS (lick the appropriate boxes)         Environitation (adderes):         Programmable room thermostal         Optimum start control           Contract control to heating         Load/weather compensation         Optimum start control         Optimum start control           Ender control to hol water         Cylinder thermostal and programmer/timer         Commissioning date         Not required           Ender control to hol water         Cylinder thermostal and programmer/timer         Contract control to heating         Not required           Ender control to hol water         Cylinder thermostal and programmer/timer         Contract control to heating         Not required           Ender control to hol water         Cylinder thermostal and programmer/timer         Room Not required         Not required           Ender control to hol water         Cylinder thermostal mater control to heating         Not required         Not required           Ender control kol water waters         Filted         Not required         Not required         Not required <td></td> <td></td> <td></td> <td>_</td> <td></td>				_														
Company name:         Telephone number:																		
Campany address:																		
Commissioning date:           To be completed by the custome roteipt of a Building Regulations Compliance Certificate?           Building Regulations Number (it applicable):           CONTROLS (lick the appropriate boxes)           Time and temperature control to hevating         Room thermostat and programmer/timer           Laddweather complemenation         Optimum start control           Mainting Start         Filted           Not required         Not required           Mainting Start         Filted           Not required         Not required           Boiler intertock         Filted         Not required           Central heading from tenseaure and record:         Gas rate         Filted         No           Boar rate warene gale moducen wast	Company name: Telephone number:																	
To be completed by the customer on receipt of a Building Regulations Compliance Certificate*         Building Regulations Notification Number of applicabile):         CONTROLS (lick the appropriate boxes)         Time and temperature control to heating       Room thermostat and programmer/timer       Programmable room thermostat         Ime and temperature control to heating       Cylinder thermostat and programmer/timer       Combination Boiler         Heating zone valves       Fitted       Not required         Hormostatic radiotra valves       Fitted       Not required         Control to by a static valves       Fitted       Not required         Automatic valves       Fitted       Not required         Boiler interlock       Fitted       Not required         Materia base flashed and cleaned in accordance with BS7593 and boler manufacturer's instructions       Yes       No         Value system flash and cleaned in accordance with BS7593 and boler manufacturer's instructions       Yes       No         Restrict HEATING MODE measure and recert:       Gas rate       Mon       Physica         Burne operating pressure (f applicable)       mbar       OR Gas intel pressure at maximum.       "Control Heating flash been installed"       "Control Heating flash been installed"         Sectratal heating flow temperature       "Control Heating flash been installed"       "Control Heating flash been	Company address:																	
Building Regulations Notifications Number (if applicable):																		
CONTROLS (tick the appropriate hoxes)         Room thermostal and programmer/time         Programmable room thermostal Optimums start control           Time and temperature control to heating         Load/weather compensation         Optimums start control           Time and temperature control to how water         Cylinder thermostal and programmer/time         Optimums start control           Heating zone valves         Fitted         Not required           Thermostatic radiator valves         Fitted         Not required           Automatic bypass to system         Fitted         Not required           Bolier inferiods         Provided         Provided           All SYSTEMS         The system has been flushed and cleaned in accordance with BS7593 and boler manufacturer's instructions         Yes           What system Genear was used?         Quantity         litter           What system Genear was used?         Quantity         litter           Central heating flow temperature         'C'C         C'C           Can rate         mithing flow temperature         'C'C           Contral heating flow temperature         'C'C	To be completed by the customer on receipt of a Building Regulations Compliance Certificate*																	
Room thermostat and programment/time         Programmable room thermostat         Optimum state control is not wate control to hot wate Cylinder thermostat and programment/time         Optimum state control is not wate control to hot wate Cylinder thermostat and programment/time         Programmable room thermostat           Heading zone valves         Fitted         Image: Control to hot wate control to hot wate control to hot wate Cylinder thermostat and programment/time         Not required           Hot water zone valves         Fitted         Image: Control to hot wate control	Building Regulations Notification Number	er (if applicable)	:				_											
Time and temperature control to hot water         Cylinder thermostat and programmer/timer         Combination Boile           Time and temperature control to hot water         Cylinder thermostat and programmer/timer         Combination Boile           Heating zone valves         Fitted         Immediate and set of the	CONTROLS (tick the appropriate boxes	3)																
Lada/weather compresation         Compresation <th< td=""><td colspan="11">Room thermostat and programmer/timer Programmable room thermostat</td><td></td></th<>	Room thermostat and programmer/timer Programmable room thermostat																	
Heating zone valves         Fitted         Not required           How water zone valves         Fitted         Not required           Automatic Dypass to system         Fitted         Not required           Boiler interfacek         Fitted         Not required           Automatic Dypass to system         Fitted         Not required           Boiler interfacek         Provided         Provided           ALL SYSTEMS         Ouantity         Itres           The system has been flushed and cleaned in accordance with BS7593 and boiler manufacturer's instructions         Yes         No           Has a primary water system filter been installed?         Ouantity         Itres           What inhibitor was used?         Wohl mobility         No         Rt/Provided           CENTRAL HEATING MODE measure and record:         Gas rate         m*Vhr         OR         Rt/Provided         No           Burner operaling pressure (if applicable)         mbar         OR Gas inlet pressure         "CC         "CC           Central heating flow temperature         "CC         "CC         "CC         Mo         Mo           Uses, and if required by the manufacturer, has a water scale reducer been fitted?         Yes         No         Mo           Uses, and if requiried by the manufacturer, has a water scale reducer b	Time and temperature control to heating	3		I	Load/wea	ther cor	npensa	ation					0	ptimun	n start c	ontrol		
Hot water zone valves         Fitted         Image: State valves         Not required           Image: State valves         Fitted         Image: State valves         Not required           Boiler interfock         Fitted         Image: State valves         Not required           ALL SYSTEMS         The system has been flushed deaned in accordance with BS7593 and boiler manufacturer's instructions instructions instructions instructions instructions         Yes         Not required           Mat system Geaner was used?         Quantity         Itrees         Itrees           Gas rate         m?hr         OR Gas intel pressure         m?hr           Burner operating pressure (f applicable)         mbr         OR Gas intel pressure         m?hr           Central heating from temperature         "C         "C         C           Combination in a hard water area (above 200ppn?)?         Yes         No         No           What type of scale reducer has been fitted?         Yes         No         No           Dot water installation in a hard water area (above 200ppn)?         Yes         No         Marea           Use installation in a hard water area (above 200ppn)?         Yes         No         Marea           Use installation in a hard water area (above 200ppn)?         Yes         No         Marea           Other	Time and temperature control to hot was	ter	Cylind	er therm	ostat and	progra	nmer/t	imer						Comb	ination	Boiler		
Hot water zone valves         Fitted         Image: State valves         Not required           Image: State valves         Fitted         Image: State valves         Not required           Boiler interfock         Fitted         Image: State valves         Not required           ALL SYSTEMS         The system has been flushed deaned in accordance with BS7593 and boiler manufacturer's instructions instructions instructions instructions instructions         Yes         Not required           Mat system Geaner was used?         Quantity         Itrees         Itrees           Gas rate         m?hr         OR Gas intel pressure         m?hr           Burner operating pressure (f applicable)         mbr         OR Gas intel pressure         m?hr           Central heating from temperature         "C         "C         C           Combination in a hard water area (above 200ppn?)?         Yes         No         No           What type of scale reducer has been fitted?         Yes         No         No           Dot water installation in a hard water area (above 200ppn)?         Yes         No         Marea           Use installation in a hard water area (above 200ppn)?         Yes         No         Marea           Use installation in a hard water area (above 200ppn)?         Yes         No         Marea           Other	Heating zone valves						F	itted							Not red	uired		
Thermostatic radiator valves         Fitted         Not required           Automatic byposs to system         Fitted         Not required         Not required           Boiler interiock         Provided         Provided         Provided           ALL SYSTEMS         State							F	itted							Not red	uired		
Automatic bypass to system         Fitted         Not required           Boile rindrack         Provided         Provided         Provided           ALL SYSTEMS         Image: State	Thermostatic radiator valves						F	itted										
Boiler interlock         Provided           ALL SYSTEMS         The system has been flushed and cleaned in accordance with BS7593 and boiler manufacturer's instructions         Ves           What system cleaner was used?         Quantity         litres           What inhibitor was used?         Quantity         litres           CENTRAL HEATING MODE measure and record:         Gas rate         n*/hr         OR         d*/hr           Burner oparating pressure (if applicable)         mbar         OR Gas inlet pressure         mbar         CC           Central heating flow temperature         ''C'         Central heating flow temperature         'C'         CC           Combinition in a hard water area (above 200ppm?         Yes         No         mbar         No         mbar           ODIESTIC HOT WATER MODE Measure and Record:         m?/hr         OR         R         ft?/hr           Doinest CHOT water MODE Measure and Record:         Contral heating flow temperature         ''C'         Yes         No         in           Gas rate         m?/hr         OR         R         ft?/hr         Main tracturer, has a water scale reducer been fitted?         ''C'           Constant ChOT WATER MODE Measure and Record:         Concert was been fitted?         Ves         No         C''C'           Cold water in																		
ALL SYSTEMS         The system has been flushed and cleaned in accordance with BS7593 and boiler manufacturer's instructions       Yes         What system cleaner was used?       Quantity       litres         What system filter been installed?       Yes       No         CENTRAL HEATING MODE measure and record:       What system filter been installed?       What system cleaner was used?         Central heating resure (if applicable)       mbar       OR       R*/hr         Burner operating pressure (if applicable)       mbar       OR Gas inlet pressure       *C         Central heating return temperature       *C       *C       *C       *C         Collemation in a hard water area (above 200ppm)?       Yes       No       *C       *C         Vipsa, and if required by the manufacturer, has a water scale reducer been fitted?       Yes       No       *C         DOMESTIC HOT WATER MODE Measure and Record:       Gas inlet pressure (at maximum rate)       mbar       OR Gas inlet pressure at maximum rate       mbar         Cold water inlet temperature       Yes       Temperature       *C       *C         Cold water inlet temperature       Yes       Temperature       *C         Cold water inlet temperature       Yes       Temperature       *C         Cold water inlet temperature       CO								litto u										
The system has been flushed and cleaned in accordance with BS7593 and boiler manufacturer's instructions         Yes           What system cleaner was used?         Quantity         litres           What system filter been installed?         Quantity         litres           Bas a primary water system filter been installed?         Quantity         litres           CENTRAL HEATING MODE measure and record:         m²ħr         OR         ft?hr           Burner operating pressure (if applicable)         mbar         OR Gas inlet pressure         mbar           Central heating flow temperature         °C         °C         record           Central heating flow temperature         °C         °C         °C           Combinition in a hard water area (above 200ppm)?         Yes         No         record           If yes, and if required by the manufacturer, has a water scale reducer been fitted?         Yes         No         record           DomeStric HOT WATER MODE Measure and Record:         Cord         ref/hr         ref/hr           Gas rate         m²hr         OR         Gas inlet pressure at maximum rate         ref/hr           DomeStric HOT WATER MODE Measure and Record:         Cord         ref/hr         ref/hr           Gas rate installed in accordance with the manufacturer's instructions and/or BS546//BS6798         Yes							_									videu	_	
What system cleaner was used?       Quantity       No         What inhibitor was used?       Quantity       No         CENTRAL HEATING MODE measure and record:       Gas rate       m?h/m       OR       Gas inlet pressure       M?h/m         Burner operating pressure (if applicable)       mbar       OR Gas inlet pressure       m?h/m       CC         Central heating flow temperature																		
What inhibitor was used?         Quantity         litres           Has a primary water system filter been installed?         Yes         No           CENTRAL HEATING MODE measure and record:         mi/hr         OR         ft/hr           Gas rate         mi/hr         OR         ft/hr           Burner operating pressure (if applicable)         mbar         OR Gas inlet pressure         ft/hr           Central heating return temperature         'CC         'CC         Combination in a hard water area (above 200ppm)?         Yes         No           If yes, and if required by the manufacturer, has a water scale reducer been fitted?         Yes         No         Vhat type of scale reducer has been fitted?           Vhat type of scale reducer has been fitted?         Yes         No         Vhat type of scale reducer has been fitted?           Cold water inleit temperature         m/hr         OR         Gas inlet pressure at maximum rate         m/hr           Gas rate         m/hr         OR         Itemperature         'CC         'CC           Cold water inleit temperature         Yes         Itemperature         'CC         'CC           Cold water inleit temperature         Yes         Itemperature         'CC         'CC           Cold water inleit temperature         Yes         Itemperature		ied in accordance	ce with BS	S7593 ar	nd boiler n	nanufac	turer's	instru	uctions							Yes		
Has a primary water system filter been installed?         Ves         No           CENTRAL HEATING MODE measure and record:         m³/hr         OR         ft?/hr           Gas rate         m³/hr         OR         ft?/hr           Burner operating pressure (if applicable)         mbar         OR Gas inlet pressure         mbar           Central heating flow temperature         *CC         *CC         *CC           Contral heating flow temperature         *CC         *CC         *CC           Contral heating flow temperature         *CC         *CC         *CC           Contral heating return temperature         *CC         *CC         *CC           Contral heating return temperature         *CC         *CC         *CC           Mast yof scale reducer has been fitted?         Yes         No         *           Vhat type of scale reducer has been fitted?         *Yes         No         *           DomESTIC HOT WATER MODE Measure and Record:         ************************************																		
CENTRAL HEATING MODE measure and record:         m?hr         OR         ft?hr           Gas rate         m?hr         OR         ft?hr           Burner operating pressure (if applicable)         mbar         OR Gas inlet pressure         mbar           Central heating flow temperature         "C         "C         "C           Central heating return temperature         "C         "C         "C           COMEINATION BOILERS ONLY         ts the installation in a hard water area (above 200ppm)?         Yes         No           If yes, and if required by the manufacturer, has a water scale reducer been fitted?         Yes         No         If yes, and if required by the manufacturer, has a water scale reducer been fitted?         Yes         No         If yes, and if required by the manufacturer, has a water scale reducer been fitted?         Yes         No         If yes, and if required by the manufacturer, has a water scale reducer been fitted?         Yes         No         If yes, and if required by the manufacturer, has a water scale reducer been fitted?         Yes         No         If yes, and if required by the manufacturer, has a water scale reducer been fitted?         Yes         No         If yes, and if required by the manufacturer, has a water scale reducer been fitted?         Yes         If yes </td <td>What inhibitor was used?</td> <td></td> <td>Quant</td> <td>ity</td> <td></td> <td>li</td> <td>tres</td>	What inhibitor was used?												Quant	ity		li	tres	
Gas rate         m²/nr         OR         ft?/nr           Burner operating pressure (if applicable)         mbar         OR Gas inlet pressure         mbar           Central heating flow temperature         "C         "C           Central heating return temperature         "C         "C           Combination BolLERS ONLY         Ves         No         If           If yes, and if required by the manufacturer, has a water scale reducer been fitted?         Yes         No         If           What type of scale reducer has been fitted?         Ves         No         If         P//nr           Gas rate         m³/nr         OR         Rearrant         Mo/         If           Guide reducer has been fitted?         Umbar         OR         If         P//nr         No         If           Burner operating pressure (at maximum rate)         mbar         OR         Gas inlet pressure at maximum rate         mbar           Cold water inlet temperature         Ves         Ves         Temperature         "C         Water flow rate         "C           It water flat temperature         Yes         Temperature         "C         Water flow rate         "Minin. rate:         CO         ppm         AND         CO/CO2         Ratio           It un	Has a primary water system filter been i	installed?											Yes			No		
Burner operating pressure (if applicable)         mbar         OR Gas inlet pressure         mbar           Central heating flow temperature         "C           Central heating return temperature         "C           Combination BOILERS ONLY         "C           Is the installation in a hard water area (above 200ppm)?         Yes         No         C           If yes, and if required by the manufacturer, has a water scale reducer been fitted?         Yes         No         C           DMESTIC HOT WATER MODE Measure and Record:         To Record It enducer has been fitted?         To Record It enducer has been fitted?         To Record It enducer has been fitted?         To Record It enducer has been checked at all outlets         Yes         To Record It enducer has been installed in accordance with the manufacturer's instructions and/or BS5546/BS6798         Yes         Yes           CONDENSING BOILERS ONLY         Temperature         "CC         Yes         Yes         Yes           At max. rate:         CO         pm         AND         CO/CO2         Ratio         Yes         To Record the following:         Yes         Temperature         Yes         Y	CENTRAL HEATING MODE measure a	and record:																
Central heating flow temperature       *C         Central heating return temperature       *C         ComBINATION BOILERS ONLY       *C         Is the installation in a hard water area (above 200ppm)?       Yes       No         If yes, and if required by the manufacturer, has a water scale reducer been fitted?       Yes       No         What type of scale reducer has been fitted?       Yes       No         DOMESTIC HOT WATER MODE Measure and Record:       GR Gas inlet pressure at maximum rate       mbar         Burner operating pressure (at maximum rate)       mbar       OR Gas inlet pressure at maximum rate       mbar         Cold water inlet temperature       Yes       Temperature       *C         Water flow rate       Yes       Temperature       *C         CONDENSING BOILERS ONLY       Temperature       *C         Muter flow rate       Yes       Temperature       *C         Muter flow rate       Yes       ManD       CO/CO2       Ratio         At max. rate:       CO       ppm       AND       CO/CO2       Ratio         The boiler and associated products have been installed and commissioned in accordance with the manufacturer's instructions       Yes       Yes         The boiler and associated products have been demonstrated to and understood by the customer       Yes <td>Gas rate</td> <td></td> <td></td> <td></td> <td></td> <td>m³/h</td> <td>r</td> <td></td> <td>c</td> <td>R</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>f</td> <td>t³/hr</td>	Gas rate					m³/h	r		c	R						f	t³/hr	
Central heating return emperature       °C         COMBINATION BOILERS ONLY       Yes       No         Is the installation in a hard water area (above 200ppm)?       Yes       No         If yes, and if required by the manufacturer, has a water scale reducer been fitted?       Yes       No         DOMESTIC HOT WATER MODE Measure and Record:       Temperature       Temperature         Gas rate       m³/hr       OR Gas inlet pressure at maximum rate       mbar         Dold stater has been checked at all outlets       Yes       Temperature       °C         Cold water has been checked at all outlets       Yes       Temperature       °C         Water flow rate       Yes       Temperature       °C         Condensate drain has been installed in accordance with the manufacturer's instructions and/or BS5546/BS6798       Yes       ALL INSTALLATIONS         Record the following:       At max. rate:       CO       ppm       AND       CO/CO2       Ratio         The bailing and hot water system complies with the appropriate Building Regulations       Yes       Tes       Tes         The bailing and hot water system complies with the appropriate Building Regulations       Yes       Yes       Tes         The bailer and associated products have been installed and commissioned in accordance with the manufacturer's instructions       Yes <td< td=""><td>Burner operating pressure (if applicable</td><td>•)</td><td></td><td></td><td></td><td>mba</td><td>r</td><td>C</td><td><b>)R</b> Gas in</td><td>let pre</td><td>ssure</td><td></td><td></td><td></td><td></td><td>n</td><td>nbar</td></td<>	Burner operating pressure (if applicable	•)				mba	r	C	<b>)R</b> Gas in	let pre	ssure					n	nbar	
COMBINATION BOILERS ONLY         Yes       No         Is the installation in a hard water area (above 200ppm)?       Yes       No         If yes, and if required by the manufacturer, has a water scale reducer been fitted?       Yes       No         What type of scale reducer has been fitted?         DOMESTIC HOT WATER MODE Measure and Record:         Gas rate       m*/hr       OR       ft*/hr         BOMESTIC HOT WATER MODE Measure and Record:         Gas rate       m*/hr       OR       ft*/hr         BOMESTIC HOT WATER MODE Measure and Record:         Gas rate       m*/hr       OR       ft*/hr         BOMESTIC HOT WATER MODE Measure and Record:         Coldwater inlet temperature       OR Gas inlet pressure at maximum rate       mbar         Coldwater inlet temperature       Yes       Temperature       *C         Water flow rate       Yes       Temperature       *C         Water flow rate       I/min         Coldwater inlet temperature       *C         Mater is been installed in accordance with the manufacturer's instructions and/or BS5546/BS6798       Yes       Mater <td col<="" td=""><td>Central heating flow temperature</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td>°C</td></td>	<td>Central heating flow temperature</td> <td></td> <td>°C</td>	Central heating flow temperature																°C
Is the installation in a hard water area (above 200ppm)?       Yes       No         If yes, and if required by the manufacturer, has a water scale reducer been fitted?       Yes       No         What type of scale reducer has been fitted?       Yes       No         OPMESTIC HOT WATER MODE Measure and Record:         Gas rate       m³/hr       OR       ft*/hr         Burner operating pressure (at maximum rate)       mbar       OR Gas inlet pressure at maximum rate       mbar         Cold water inlet temperature       Yes       Temperature       °C         Ho water has been checked at all outlets       Yes       Temperature       °C         Water flow rate       If max. rate:       CO       ppm       AND       CO/CO2       Ratio         Cold water system complies with the appropriate Building Regulations       Yes       Tes         The boiler and associated products have been installed and commissioned in accordance with the manufacturer's instructions by the customer       Yes       Yes         The operation of the boiler and system complies externed backed and service Record, has been explained and left with the customer       Yes       Yes         Commissioning Engineer's Signature       Commissioning Engineer's Signature       Yes       Yes       Yes	Central heating return temperature																°C	
Is the installation in a hard water area (above 200ppm)?       Yes       No         If yes, and if required by the manufacturer, has a water scale reducer been fitted?       Yes       No         What type of scale reducer has been fitted?       Yes       No         OPMESTIC HOT WATER MODE Measure and Record:         Gas rate       m³/hr       OR       ft*/hr         Burner operating pressure (at maximum rate)       mbar       OR Gas inlet pressure at maximum rate       mbar         Cold water inlet temperature       Yes       Temperature       °C         Ho water has been checked at all outlets       Yes       Temperature       °C         Water flow rate       If max. rate:       CO       ppm       AND       CO/CO2       Ratio         Cold water system complies with the appropriate Building Regulations       Yes       Tes         The boiler and associated products have been installed and commissioned in accordance with the manufacturer's instructions by the customer       Yes       Yes         The operation of the boiler and system complies externed backed and service Record, has been explained and left with the customer       Yes       Yes         Commissioning Engineer's Signature       Commissioning Engineer's Signature       Yes       Yes       Yes	COMBINATION BOILERS ONLY																_	
If yes, and if required by the manufacturer, has a water scale reducer been fitted?       Yes       No         What type of scale reducer has been fitted?       DOMESTIC HOT WATER MODE Measure and Record:       It is a water scale reducer has been fitted?         DOMESTIC HOT WATER MODE Measure and Record:       It is a water scale reducer has been fitted?       OR       It is a water scale reducer has been fitted?         Domestic Hor water and persaure (at maximum rate)       mbar       OR Gas inlet pressure at maximum rate       mbar         Cold water inlet temperature       fit water has been checked at all outlets       Yes       Temperature       °C         Hot water has been installed in accordance with the manufacturer's instructions and/or BS5546/BS6798       Yes       Temperature       °C         At max. rate:       CO       ppm       AND       CO/CO2       Ratio       Temperature       Yes       Temperature       Yes       Temperature       Yes       Temperature       °C       Yes       Temperature       °C       Yes       Yes       Temperature       °C       Yes       Temperature       °C       Yes       Yes       Temperature       °C       Yes       Yes       Temperature       °C       Yes       Temperature       °C       Yes       Temperature       °C       Yes       Temperature       °C       Yes <td></td> <td>above 200ppm)'</td> <td>2</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>Yes</td> <td></td> <td></td> <td>No</td> <td></td>		above 200ppm)'	2										Yes			No		
What type of scale reducer has been fitted?         DOMESTIC HOT WATER MODE Measure and Record:         Gas rate       m³/hr         Gas rate       m³/hr         Burner operating pressure (at maximum rate)       mbar         OR Gas inlet pressure at maximum rate       mbar         Cold water inlet temperature       °C         Hot water has been checked at all outlets       Yes       Temperature       °C         Water flow rate       I/min       I/min       °C         CONDENSING BOILERS ONLY       If and a coordance with the manufacturer's instructions and/or BS5546/BS6798       Yes       I/min         ALL INSTALLATIONS       At max. rate:       CO       ppm       AND       CO/CO2       Ratio         The boiler and associated products have been installed and commissioned in accordance with the manufacturer's instructions       Yes       Yes       The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes       Yes       Yes         The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes       Yes         Commissioning Engineer's Signature       Ves       Yes       Yes       Yes	· · · · · · · · · · · · · · · · · · ·			ucer hee	n fitted?													
DOMESTIC HOT WATER MODE Measure and Record:         Gas rate       m³/hr       OR       R       ft²/hr         Burner operating pressure (at maximum rate)       mbar       OR Gas inlet pressure at maximum rate       mbar         Cold water inlet temperature       °C       °C       °C         Hot water has been checked at all outlets       Yes       Temperature       °C         Water flow rate       Yes       Temperature       °C         Condensate drain has been installed in accordance with the manufacturer's instructions and/or BS5546/BS6798       Yes          ALL INSTALLATIONS       At max. rate:       CO       ppm       AND       CO/CO2       Ratio         The heating and hot water system complies with the appropriate Building Regulations       Yes       Yes          The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes       Yes         The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes       Yes         Commissioning Engineer's Signature       Yes       Yes       Yes													100			110		
Case rate       m³/hr       OR       ft²/hr         Burner operating pressure (at maximum rate)       mbar       OR Gas inlet pressure at maximum rate       mbar         Cold water inlet temperature       OR Gas inlet pressure at maximum rate       mbar       °C         Hot water has been checked at all outlets       Yes       Temperature       °C         Water flow rate       Yes       Temperature       °C         CONDENSING BOILERS ONLY       Temperature 's instructions and/or BS5546/BS6798       Yes       Yes         ALL INSTALLATIONS       At max. rate:       CO       ppm       AND       CO/CO2       Ratio         Record the following:       At max. rate: (where possible)       CO       ppm       AND       CO/CO2       Ratio         The heating and hot water system complies with the appropriate Building Regulations       Yes       Yes       The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes       Yes       The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes       Yes       The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes       Yes         Commissioning Engineer's Signature       Yes       Commissioning Engineer's Signature       Yes																		
Burner operating pressure (at maximum rate)       mbar       OR Gas inlet pressure at maximum rate       mbar         Cold water inlet temperature       °C         Hot water has been checked at all outlets       Yes       Temperature       °C         Water flow rate       Yes       Temperature       °C         CONDENSING BOILERS ONLY       I/min       I/min       I/min       I/min         Condensate drain has been installed in accordance with the manufacturer's instructions and/or BS5546/BS6798       Yes       I/min         ALL INSTALLATIONS         Record the following:       At max. rate:       CO       ppm       AND       CO/CO2       Ratio         The heating and hot water system complies with the appropriate Building Regulations       Yes       Yes       Yes       Yes         The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes       Yes       Yes         The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes       Yes       Yes         Commissioning Engineer's Signature       Yes       Yes       Yes       Yes       Yes       Yes			•			m3/b	-						1				43/br	
Cold water inlet temperature       °C         Hot water has been checked at all outlets       Yes       Temperature       °C         Water flow rate       I/min         CONDENSING BOILERS ONLY       I/min         The condensate drain has been installed in accordance with the manufacturer's instructions and/or BS5546/BS6798       Yes       I/min         ALL INSTALLATIONS       Immediate the following:       At max. rate:       CO       ppm       AND       CO/CO2       Ratio         The heating and hot water system complies with the appropriate Building Regulations       Yes       Yes       Immediate the following:       Yes         The boiler and associated products have been installed and commissioned in accordance with the manufacturer's instructions       Yes       Yes         The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes       Yes         The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes       Yes         Commissioning Engineer's Signature       Yes       Yes       Yes       Yes								Casi										
Hot water has been checked at all outlets       Yes       Temperature       °C         Water flow rate       I/min         CONDENSING BOILERS ONLY         The condensate drain has been installed in accordance with the manufacturer's instructions and/or BS5546/BS6798       Yes       Yes         ALL INSTALLATIONS         Record the following:       At max. rate:       CO       ppm       AND       CO/CO2       Ratio         The heating and hot water system complies with the appropriate Building Regulations       Yes       Yes       The boiler and associated products have been installed and commissioned in accordance with the manufacturer's instructions       Yes       Yes         The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes         The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes         Commissioning Engineer's Signature		(Tale)				IIIDa	UK	Gasi	liet press	uleat	maxin	ium rate	•			11		
Water flow rate       I/min         CONDENSING BOILERS ONLY         The condensate drain has been installed in accordance with the manufacturer's instructions and/or BS5546/BS6798       Yes         ALL INSTALLATIONS         Record the following:       At max. rate:       CO       ppm       AND       CO/CO2       Ratio         The heating and hot water system complies with the appropriate Building Regulations       Yes         The boiler and associated products have been installed and commissioned in accordance with the manufacturer's instructions       Yes         The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes         The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes         Commissioning Engineer's Signature         Customer's Signature		4-										/						
CONDENSING BOILERS ONLY         The condensate drain has been installed in accordance with the manufacturer's instructions and/or BS546/BS6798       Yes         ALL INSTALLATIONS         Record the following:       At max. rate:       CO       ppm       AND       CO/CO2       Ratio         The heating and hot water system complies with the appropriate Building Regulations       Yes         The boiler and associated products have been installed and commissioned in accordance with the manufacturer's instructions       Yes         The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes         The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes         Commissioning Engineer's Signature		ts										res	Iem	iperatu	ire		-	
ALL INSTALLATIONS       Yes         ALL INSTALLATIONS       At max. rate:       CO       ppm       AND       CO/CO2       Ratio         Act max. rate:       CO       ppm       AND       CO/CO2       Ratio       Image: CO/CO2       Ratio         The heating and hot water system complies with the appropriate Building Regulations       CO/CO2       Ratio       Yes       Image: CO/CO2       Ratio         The boiler and associated products have been installed and commissioned in accordance with the manufacturer's instructions       Yes       Yes         The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes       Yes         The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes         Commissioning Engineer's Signature       Commissioning Engineer's Signature       Ves	Water flow rate															I/	min	
ALL INSTALLATIONS         Record the following:       At max. rate:       CO       ppm       AND       CO/CO2       Ratio         At min. rate: (where possible)       CO       ppm       AND       CO/CO2       Ratio         The heating and hot water system complies with the appropriate Building Regulations       Yes         The boiler and associated products have been installed and commissioned in accordance with the manufacturer's instructions       Yes         The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes         The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes         Commissioning Engineer's Signature       Customer's Signature       Yes	CONDENSING BOILERS ONLY																	
At max. rate:       CO       ppm       AND       CO/CO2       Ratio         At min. rate: (where possible)       CO       ppm       AND       CO/CO2       Ratio         The heating and hot water system complies with the appropriate Building Regulations       Yes       Yes       Interview       Yes         The boiler and associated products have been installed and commissioned in accordance with the manufacturer's instructions       Yes       Yes         The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes       Yes         The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes         Commissioning Engineer's Signature       Customer's Signature       Ves	The condensate drain has been installe	d in accordance	with the I	manufac	turer's ins	structior	is and/	or BS	5546/BS6	6798						Yes		
Record the following:       At min. rate: (where possible)       CO       ppm       AND       CO/CO2       Ratio         The heating and hot water system complies with the appropriate Building Regulations       Yes       Yes         The boiler and associated products have been installed and commissioned in accordance with the manufacturer's instructions       Yes         The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes         The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes         Commissioning Engineer's Signature       Customer's Signature	ALL INSTALLATIONS																	
At min. rate: (where possible)       CO       ppm       AND       CO/CO2       Ratio         The heating and hot water system complies with the appropriate Building Regulations       Yes       Image: Color Colo		At max. rate:			со			ppm	AND	CO/	CO₂			Ratio	)		_	
The heating and hot water system complies with the appropriate Building Regulations       Yes         The boiler and associated products have been installed and commissioned in accordance with the manufacturer's instructions       Yes         The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes         The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes         Commissioning Engineer's Signature       Customer's Signature	Record the following:	At min. rate: (v	where pos	sible)	СО													
The boiler and associated products have been installed and commissioned in accordance with the manufacturer's instructions       Yes         The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes         The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes         Commissioning Engineer's Signature       Customer's Signature	The heating and hot water system comp		-		Regulatio	ons				1						Yes		
The operation of the boiler and system controls have been demonstrated to and understood by the customer       Yes         The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes         Commissioning Engineer's Signature       Customer's Signature				-	-		with th	e mai	nufacture	's inst	ructio	าร						
The manufacturer's literature, including Benchmark Checklist and Service Record, has been explained and left with the customer       Yes         Commissioning Engineer's Signature       Customer's Signature												-						
Commissioning Engineer's Signature Customer's Signature										with th	e cust	omer						
Customer's Signature											2 5401							
(Io contirm satisfactory demonstration and receipt of manufacturer's literature)																		
	(Io confirm satisfactory demonstration a	and receipt of m	anufactur	er's litera	ature)								—				_	

\*All installations in England and Wales must be notified to Local Authority Building Control (LABC) either directly or through a Competent Persons Scheme. A Building Regulations Compliance Certificate will then be issued to the customer.



#### SERVICE RECORD

#### It is recommended that your heating system is serviced regularly and that the appropriate Service Interval Record is completed.

#### Service Provider

Before completing the appropriate Service Record below, please ensure you have carried out the service as described in the manufacturer's instructions. Always use the manufacturer's specified spare part when replacing controls.

SERVICE 01			Date:	SER	VICE 02		Date:				
Engineer name:					Engineer	name:					
Company	name:				Compan	Company name:					
Telephone No:					Telephone No:						
Gas safe register No:						Gas safe register No:					
Descut	At max. rate:	CO ppm	AND	CO2 %	Desert	At max. rate:	CO ppm	AND	CO2 %		
Record:	At min. rate: (Where Possible)	CO ppm	AND	CO2 %	Record:	At min. rate: (Where Possible)	CO ppm	AND	CO2 %		
Commen	ts:				Commer	its:					
Signature	)				Signature	e					
CED				Deter					Data		
SER	VICE 03			Date:	JOER	VICE 04			Date:		
Engineer	name:				Engineer						
Company					Company						
Telephon					Telephor						
Gas safe	register No:	1	1		Gas safe	register No:	1				
Record:	At max. rate:	CO ppm	AND	CO2 %	Record:	At max. rate:	CO ppm	AND	CO2 %		
	At min. rate: (Where Possible)	CO ppm	AND	CO2 %		At min. rate: (Where Possible)	CO ppm	AND	CO2 %		
Commen	ts:				Commer	its:					
Signature					Signature	9					
SER	VICE 05			Date:	SER	VICE 06			Date:		
Engineer	name:				Engineer name:						
Company	name:				Company name:						
Telephon	e No:				Telephone No:						
Gas safe	register No:				Gas safe	register No:					
Record:	At max. rate:	CO ppm	AND	CO2 %	Record:	At max. rate:	CO ppm	AND	CO2 %		
Record.	At min. rate: (Where Possible)	CO ppm	AND	CO2 %	Record.	At min. rate: (Where Possible)	CO ppm	AND	CO2 %		
Commen	ts:				Commer	its:					
						-					
Signature	•				Signature	e					
SER	VICE 07			Date:	SER	VICE 08			Date:		
Engineer	name:				Engineer	name:					
Company	name:				Compan	y name:					
Telephon	e No:				Telephone No:						
Gas safe	register No:				Gas safe	register No:					
Descul	At max. rate:	CO ppm	AND	CO2 %		At max. rate:	CO ppm	AND	CO2 %		
Record:	At min. rate: (Where Possible)	CO ppm	AND	CO2 %	Record:	At min. rate: (Where Possible)	CO ppm	AND	CO2 %		
Commen	ts:				Commer	its:					
Signature	1				Signature	e					
SER	VICE 09			Date:	SER	VICE 10			Date:		
Engineer											
					Engineer name: Company name:						
Company name: Telephone No:						ie No:					
Gas safe register No:						register No:					
	At max. rate:	CO ppm	AND	CO2 %		At max. rate:	CO ppm	AND	CO2 %		
Record:	At min. rate: (Where Possible)	CO ppm		CO <sub>2</sub> %	Record:	At min. rate: (Where Possible)	CO ppm		CO <sub>2</sub> %		
Commen		ppill		00270	Commer		Phill		002 /0		
					-						
Signature					Signature						
Signatule						٠ -					

\*All installations in England and Wales must be notified to Local Authority Building Control (LABC) either directly or through a Competent Persons Scheme. A Building Regulations Compliance Certificate will then be issued to the customer.





#### Ariston Thermo UK Ltd Artisan Building

Hillbottom Road High Wycombe Bucks HP124HJ Telephone: 01494 418500

## ariston.co.uk

420010963900

Customer Service: 0333 240 8777